SPSH4 Server System

Technical Product Specification

Intel reference number 10736

Revision 1.11

March, 2003

Enterprise Platforms and Services Marketing

Downloaded from www.Manualslib.com manuals search engine

Revision History

Date	Revision Number	Modifications
6/21/01	0.5	Preliminary Draft for Review
8/20/02	1.0	Revisions to Roll to 1.0 for publication
1/2003	1.1	Revisions to include Adaptec U320 SCSI Controller 100 MHz support
March 2003	1.11	Corrected section 5.3.4 on page 45 to reflect 4Mb Video rather than 2 mb video memory to be consistent with the SRSH4 TPS

Downloaded from www.Manualslib.com manuals search engine

Disclaimers

Information in this document is provided in connection with Intel® products. No license, express or implied, by estoppel or otherwise, to any intellectual property rights is granted by this document. Except as provided in Intel's Terms and Conditions of Sale for such products, Intel assumes no liability whatsoever, and Intel disclaims any express or implied warranty, relating to sale and/or use of Intel products including liability or warranties relating to fitness for a particular purpose, merchantability, or infringement of any patent, copyright or other intellectual property right. Intel products are not intended for use in medical, life saving, or life sustaining applications. Intel may make changes to specifications and product descriptions at any time, without notice.

Designers must not rely on the absence or characteristics of any features or instructions marked "reserved" or "undefined." Intel reserves these for future definition and shall have no responsibility whatsoever for conflicts or incompatibilities arising from future changes to them.

This document contains information on products in the design phase of development. Do not finalize a design with this information. Revised information will be published when the product is available. Verify with your local sales office that you have the latest datasheet before finalizing a design.

The SPSH4 Server System may contain design defects or errors known as errata which may cause the product to deviate from published specifications. Current characterized errata are available on request.

This document and the software described in it is furnished under license and may only be used or copied in accordance with the terms of the license. The information in this manual is furnished for informational use only, is subject to change without notice, and should not be construed as a commitment by Intel Corporation. Intel Corporation assumes no responsibility or liability for any errors or inaccuracies that may appear in this document or any software that may be provided in association with this document.

Except as permitted by such license, no part of this document may be reproduced, stored in a retrieval system, or transmitted in any form or by any means without the express written consent of Intel Corporation.

Intel, Pentium, Itanium, and Xeon are trademarks or registered trademarks of Intel Corporation.

*Other brands and names may be claimed as the property of others.

Copyright © Intel Corporation 2001.

Downloaded from www.Manualslib.com manuals search engine

Table of Contents

1. Introduction 1
2. SPSH4 Server Chassis Feature Overview 2
2.1 Front Panel 5
2.2 Rear Features 7
3. Physical Specifications 9
3.1 SSH4 Boardset 11
3.2 Guidelines For Installing Memory in the SSH4 Server Board. 14
4. Power supply Subsystem 15
4.1 Mechanical Dimensions 18
4.2 Airflow Requirements 20
4.2.1 Over-Temperature Protection 20
4.2.2 Connectors and Pinouts 20
4.2.3 AC Electrical Specifications 22
4.2.4 DC Output Specification 25
4.2.5 Electrical Protection Circuits 32
4.2.6 Control Signals 33
4.3 Cooling Subsystem 38
4.3.1 Redundancy and Ambient Temperature Control 38
4.3.2 Cooling Summary 39
5. Cables and Connectors 40
5.1 Interconnect Block Diagram 40
5.2 Cable and Interconnect Descriptions 41
5.3 Operator-Accessible Interconnects 42
5.3.1 Keyboard and Mouse Ports 42
5.3.2 Serial Ports 43
5.3.3 Parallel Port 44
5.3.4 Video Port 45
5.3.5 Universal Serial Bus (USB) Interface 45
5.3.6 ICMB Connectors 46
5.3.7 100/10 Ethernet Connector (LAN 1) 46
5.3.8 1000/100/10 Ethernet Connector (LAN 2) 47
5.3.9 Internal SCA-2 HDD Connector 47

Downloaded from www.Manualslib.com manuals search engine

5.3.10 External SCSI 49
5.3.11 AC Power Input 50
6. SCSI Bay Boardset 51
6.1 Hot Swap Hard Drive Backplane 51
6.1.1 Architectural Overview 52
6.2 Design Constraints and Assumptions 52
6.2.1 SCSI Bus Considerations 52
6.3 Functional Description 53
6.3.1 Wide SCSI Connector 53
6.3.2 SCA-2 Connectors 53
6.3.3 SCSI Multi-ModeTermination 54
6.3.4 SCSI Interface 54
6.3.5 Power Control 54
6.3.6 FET Short Protection 54
6.3.7 Microcontroller 55
6.3.8 Device SCSI ID 55
6.3.9 Hard Drive Activity LED 55
6.3.10 Hard Drive Fault LED 56
6.3.11 IMB (I^2C bus) 56
6.3.12 Fan Support 56
6.3.13 Temperature 56
6.3.14 Serial EEPROM 56
6.4 Board Functions 57
6.4.1 Reset 57
6.4.2 Microcontroller 57
6.4.3 SCSI Controller 59
6.4.4 Multi-Mode SCSI Termination 59
6.5 Memory Map 59
6.5.1 Memory Map 60
6.5.2 I/O Ports 63
6.6 Programming Information 65
6.6.1 Firmware Support Requirements 66
6.7 External Interface Specifications 66
6.7.1 Connector Specifications 66
6.7.2 SCSI Input Connector 68P 67

Downloaded from www.Manualslib.com manuals search engine

6.7.3 I²C Connector 69
6.7.4 Power Connector 70
6.7.5 Fan 3-pin Connector 70
6.7.6 SAF-TE PCI Connector Interface 70
6.8 Cables 73
6.8.1 Signal Cables 73
6.8.2 Power Cables 73
6.9 Mechanical Specifications 73
7. System Boards 75
7.1 Power Distribution Board 75
7.1.1 Board Layout 76
7.1.2 Connector Pinouts 76
7.2 Front Panel Board 79
7.2.1 Board Layout 80
7.2.2 Connector Pinouts 81
7.3 Fan Distribution Board 83
7.3.1 Board Layout 83
7.3.2 Connector Pinouts 83
7.4 HPIB Board 85
7.4.1 Board Layout 86
7.4.2 Connector Pinouts 86
7.5 ICMB Board 87
7.5.1 Board Layout 87
7.5.2 Connector Pinouts 87
8. Hardware Configuration 89
8.1 System Configuration 89
8.2 Spares / Accessories 90
9. Product Regulatory Compliance Specifications 91
9.1 Product Safety Compliance 91
9.2 Product EMC Compliance 91
9.3 Regulatory Markings 92
9.4 Product Safety Markings 93
9.5 Power supply Regulatory Agency Certifications 93
9.6 Regulatory Compliance Notices, Statements and Information 94
9.6.1 USA FCC Verification Notice 94

Downloaded from www.Manualslib.com manuals search engine

9.6.2 Canada 95
9.6.3 European Union 95
9.6.4 Australia / New Zealand 95
9.6.5 Japan 95
9.6.6 Taiwan 96
9.7 Replacing The Back Up Battery 96
10. Environmental Specifications 97
11. Serviceability and Usability 98
11.1 Mean Time to Repair 98
11.2 Special Usability Features 99
12. Index V

Downloaded from www.Manualslib.com manuals search engine

List of Figures

Figure 1: Front View of Pedestal Configuration 3
Figure 2: Front View of Rack Configuration 3
Figure 3: Front View of System (Shown with Bezel Removed) 4
Figure 4: Front Panel Details (Rack Bezel Shown) 5
Figure 5: Rear View Of Chassis 7
Figure 6: SPSH4 Server System Photograph with Side Panels and Front Panel Removed 10
Figure 7: Functional Block Diagram of SSH4 Boardset 11
Figure 8: SPSH4 Power supply 16
Figure 9: Rear view of SPSH4 Power Supply Bay 17
Figure 10: SPSH4 Power supply Outline Drawing 19
Figure 11: Connector Pin Locations 21
Figure 12: Inrush Curve 25
Figure 13: Differential Noise Test Setup 29
Figure 14: Output Voltage Timing 30
Figure 15: Turn On/Off Timing 31
Figure 16: Fan Bay (Shown with all Fan Banks Installed) 38
Figure 17: SPSH4 System Interconnect Block Diagram 40
Figure 18: SCA-2 Connector 48
Figure 19: AC Power Input Connector 50
Figure 20: Functional Block Diagram 53
Figure 21: Microcontroller Memory Map 60
Figure 22: SCSI Input connector 68P Non-Shielded 67
Figure 23: SCA-2 Connector 80P 68
Figure 24: Hotswap Backplane Mechanical Drawing 73
Figure 25: SAF-TE Addin Card Mechanical Drawing 74
Figure 26: Fan Board Layout 76
Figure 27: Power supply Mating Connector Pin Locations 77
Figure 28: Fan Board Layout 80
Figure 29: Fan Board Layout 83
Figure 30: HPIB Board Layout 86
Figure 31: ICMB Board Layout 87

Downloaded from www.Manualslib.com manuals search engine

List of Tables

Table 1: Front Panel Features 6
Table 2: System Features - Rear 8
Table 3: Physical Specifications 9
Table 4: LED Indicators 18
Table 5: Airflow Requirements 20
Table 6: Signal Descriptions 21
Table 7: Output Connector Pin-out 21
Table 8: AC Input Voltage Rating 22
Table 9: AC Line Sag Transient Performance 23
Table 10: AC Line Surge Transient Performance 23
Table 11: Electrostatic Discharge, IEC 801-2/IEC 1000-4-2 23
Table 12: Electrical Fast Transient/Burst, IEC 801-4/IEC 1000-4-4 23
Table 13: Radiated Immunity, IEC 801-3/IEC1000-4-3 23
Table 14: Surge Immunity IEC 1000-4-5 24
Table 15: Ring Wave 24
Table 16: DC Output Voltage Limits 26
Table 17: 600W Load Ratings 27
Table 18: Total System Load at Line AC Input 27
Table 19: Absolute Worst Case System Power Budget 27
Table 20: Remote Sense Drops 28
Table 21: Dynamic Tolerance Requirement 28
Table 22: Ripple and Noise 29
Table 23: Output Voltage Timing 30
Table 24: Turn On/Off Timing 30
Table 25: Over-Voltage Limits 32
Table 26: Over Current Protection Limits 32
Table 27: PSON Signal Characteristic 33
Table 28: PWOK Signal Characteristics 33
Table 29: PSKILL Signal Characteristics 34
Table 30: FAIL Signal Characteristics 35
Table 31: PRFL Signal Characteristics 35
Table 32: PRESENT# Signal Characteristics 36

Downloaded from www.Manualslib.com manuals search engine

Table 33: Fan Speed Control 36
Table 34: Pins for Power supply Connector FRU Information 37
Table 35: System Interconnect Descriptions 41
Table 36: Keyboard and Mouse Ports 42
Table 37: Serial Port A Connector 43
Table 38: Parallel Port Connector 44
Table 39: Video Connector 45
Table 40: Dual USB Connector 45
Table 41: ICMB Connector 46
Table 42: Ethernet Connector 46
Table 43: Ethernet Connector 47
Table 44: SCA-2 Connector 47
Table 45: SCSI Connector 49
Table 46: SCSI ID Assignments 55
Table 47: Hard Drive Activity LED 55
Table 48: Hard Drive Fault LED 56
Table 49: Drive Power Status Byte Format 61
Table 50: Fault Indicator Control Byte Format 62
Table 51: Drive Presence Status Byte Format 62
Table 52: P1 Functions 64
Table 53: P3 Functions 65
Table 54: Connector Specifications 66
Table 55: SCSI Input connector (J1D1) 67
Table 56: SCA-2 Connectors (J3E1, J3D1, J3C1, J3B1, J3A1) 68
Table 57: I^2C Connector (J2A1) 69
Table 58: Power Connector (J4A1, J3A2) 70
Table 59: Fan Connector 70
Table 60: PCI connector (J5C1) 71
Table 61: Signal Pins and Power Blades (PS1, PS2, PS3) 76
Table 62: Main Power #1 Connector (P5) 77
Table 63: Main Power #2 Connector (P4) 77
Table 64: Main Power Control Connector (P6) 78
Table 65: Fan/Peripheral Power Connector (P1) 78
Table 66: Primary SCSI Bay Power Connector (P2) 78
Table 67: Seconday SCSI Bay Power Connector (P3) 78

Downloaded from www.Manualslib.com manuals search engine

Table 68: Front Panel Signal Connector (P5) 81
Table 69: USB Port 3 Input Connector (P7) 81
Table 70: USB Port 3 (P2) 81
Table 71: Serial Port B Input Connector (P6) 82
Table 72: RJ45 Serial Port B (P1) 82
Table 73: Chassis Intrusion Connector 1 (P4) 82
Table 74: Chassis Intrusion Connector 2 (P3) 82
Table 75: Power Connector (P5) 83
Table 76: Front 120mm Fan Bank Connector (P1) 84
Table 77: Front 80mm Fan Connector (P2) 84
Table 78: Rear 120mm Fan Bank Connector (P3) 84
Table 79: Rear 80mm Fan Connector (P4) 84
Table 80: Fan Signal Connector (P6) 85
Table 81: HPIB Signal Connector (P1) 86
Table 82: Keyed RJ45 ICMB Port Connectors (P1 & P2) 87
Table 83: ICMB Signal Connector to Baseboard (P3) 88
Table 84: System Configuration 89
Table 85: Spare / Accessory List 90
Table 86: Product Safety Compliance 91
Table 87: Product EMC Compliance 91
Table 88: Regulatory Markings 92
Table 89: Product Safety Markings 93
Table 90: Environmental Specifications Summary 97

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

1. Introduction

This product specification details the features of the SPSH4 server system. Low cost, time to market, modularity, and utilization for multiple configurations are primary considerations in the design. The chassis has user friendly features and is accessible and serviceable.

The SPSH4 server system also incorporates features for high availablity servers. This includes power and cooling systems with optional redundancy, hot swap or easy to replace fans hot-plug PCI slots, and a mass storage system with hot-swappable hard drives. These are the key components for increasing availability of the server. Since the fans and power supplies typically have the lowest Mean Time Between Failure (MTBF) specifications, the optional redundancy of these components will permit the system to continue to operate with a failed fan or power supply. With the use of RAID technology the system can continue to operate with hard drive failures The hot-plug hard drives allow a failed hard drive to be replaced while the system continues to operate.

This product specification details the following:

- SPSH4 chassis features.
- Power supply subsystem.
- Chassis cooling.
- Front panel.
- System boards.
- I/O and interconnects.
- System configuration.
- System Certifications.
- Environmental limits.
- Reliability, serviceability, and availability.

Downloaded from www.Manualslib.com manuals search engine

2. SPSH4 Server Chassis Feature Overview

The SPSH4 MP server Chassis is 12.22 inches wide, 18.06 inches high, and 25.25 inches deep. The chassis is designed to be modular with a base unit with two easily removable units, one to hold the front panel and drive bays (C-tilt) and one to hold the baseboard, processor board and I/O panels (E-Bay). The Base section is U shaped and holds the power supplies and power distribution board. The E-bay drops in at the rear of the base unit and the C-tilt drops in from the front. The two captive screws in the front cover fasten both the E-bay and the C-tilt to the base unit. The E-bay fans are plugged in to a hot-swap fan holder and installed above the drives and infron to the E-bay. Three bays are supplied in the back of the chassis base unit for power supplies.

Figure 1 and Figure 2 show the system front view with both rack and pedestal bezel attached. The rack bezel has the standard color specific GE Cycoloy C6600-701 black. The pedestal bezel comes in two colors and has the standard color specific of GE Cycoloy C6600-701 black or GE Cycoloy C6600-BR7026 dusty beige. Only front panel status LEDs and chassis security lock are visible without opening bezel door. Figure 3 shows the system front view with the front bezel removed. Opening the front bezel door provides access to the following:

- Front panel control buttons
- One USB and one serial port
- Three 5¼” device bays (one 5¼” CD-ROM installed)
- One 3½” bay for a 1” floppy drive
- Two SCSI bays holding up to ten 1” hard drives

Downloaded from www.Manualslib.com manuals search engine




Figure 1: Front View of Pedestal Configuration




Figure 2: Front View of Rack Configuration

Downloaded from www.Manualslib.com manuals search engine




Figure 3: Front View of System (Shown with Bezel Removed)

Downloaded from www.Manualslib.com manuals search engine

2.1 Front Panel

The front panel contains system control switches and status indicators. Front panel features are shown in Figure 4 and are described in Table.




Figure 4: Front Panel Details (Rack Bezel Shown)

Downloaded from www.Manualslib.com manuals search engine

Table 1 Front Panel Features

Feature	Description
Front Panel Button	
Reset	Resets system power.
Sleep	Activates the sleep mode.
NMI *(Hidden Behind Bezel)*	Causes a non-maskable interrupt. This switch is located behind the front bezel door to prevent inadvertent activation. The front bezel door must be opened to access this switch. A narrow tool is required to activate the switch.
Power	Toggles system power.
Chassis ID	Activates the chassis LED on both the front panel board and on the baseboard at the rear panel of the chassis.
Front Panel LEDs	
Chassis ID (blue)	Indicates that matching chassis ID LED will be present at rear panel of chassis to ease identification when servicing rear of system in a rack.
Power (green)	When continuously lit, indicates the presence of DC power in the server. The LED goes out when the power is turned off or the power source is disrupted. When flashing it indicates the system is in ACPI sleep mode.
HDD Activity/Fault (green/amber)	Indicates any system hard drive activity or fault condition.
LAN1 (green)	Indicates 100/10Mb Ethernet port activity.
LAN2 (green)	Indicates 1000/100/10Mb Ethernet port activity.
System Status/Fault (green/amber)	Indicates system status or fault condition.
Front Panel IO Connectors	
USB Connector	USB port 3
RJ45 Connector	Serial port B.

Downloaded from www.Manualslib.com manuals search engine

2.2 Rear Features




Figure 5: Rear View Of Chassis

Downloaded from www.Manualslib.com manuals search engine

Table 1: System Features - Rear

Item	Description
A	Optional External VHDCI SCSI port
B	Optional External SCSI3 port
C	Optional ICMB connector ports, keyed RJ45 8-pin connector
D	Hot Plug PCI-X Power/Fault LEDs
E	Two non hot plug 32-bit, 33 MHz PCI add-in card slots
F	Two non hot plug 64-bit, 100 MHz PCI-X add-in card slots
G	Four hot plug 64-bit, 100 MHz PCI-X add-in card slots
H	Filler panel for power bay 3
I	Power supply 2
J	Power supply IEC320-C14 AC inlet
K	Power supply 1
L	Power supply on LED (Green)
M	Power supply predictive failure LED (Amber)
N	Power supply failure LED (Amber)
O	LAN1 100/10 RJ45 connector
P	Knockout for optional serial port B, 9-pin RS-232 connector
Q	LAN2 Gigabit port (1000/100/10)
R	USB ports 1 (upper) and 2 (lower), 4-pin connectors
S	Video connector
T	Serial port A, 9-pin RS-232 connector
U	PS/2-compatible parallel port (LPT), 25-pin bi-directional subminiature D connector
V	PS/2-compatible mouse port, 6-pin connector
W	PS/2-compatible keyboard port, 6-pin connector
X	Chassis ID LED (Blue)

Downloaded from www.Manualslib.com manuals search engine

3. Physical Specifications

Table 2 describes the physical specifications of the SPSH4 system.

Table 2: Physical Specifications

Specification	Black or Beige Pedestal Value	Rack Value
Height	18.06 inches with feet	7U
Width	12.22 inches	Fits 19” standard rack
Depth	25.25 inches	25.25 inches
Clearance Front	3 inches	3 inches
Clearance Rear	4.5 inches	4.5 inches
Clearance Side	0 inches	0 inches
Weight	90 lbs. minumum / 125 lbs. maximum configuration	96 lbs. minumum / 125 lb. Maximum configuration
Heat Output	3686 BTU/hr (typical)	3686 BTU/hr (typical)

Downloaded from www.Manualslib.com manuals search engine



Figure 6: SPSH4 Server System Photograph with Side Panels and Front Panel Removed

Downloaded from www.Manualslib.com manuals search engine

3.1 SSH4 Boardset

This section highlights the main features of the SSH4 baseboard, memory board and processor board Refer to the *SSH4 Baseboard, Processor Board and Memory Module Technical Product Specification* for a detailed description of the SSH4 baseboard.




Figure 7: Functional Block Diagram of SSH4 Boardset

The SSH4 boardset is designed around the Intel® MP Xeon™ processor and the ServerWorks* ServerSet* IV Grand Champion High End (GCHE) chipset. This combination provides the basis for a high performance system with leading edge processor, memory, and I/O performance.

The SSH4 baseboard architecture supports quad processing operation using Intel Intel MP Xeon processors. It also provides eight industry standard PCI expansion slots supporting a mixture of 32-bit, 33MHz (two), and 64-bit, 100/66 MHz (six) slots. The baseboard includes an array of embedded I/O devices, see figure 8 and table 4 below

Downloaded from www.Manualslib.com manuals search engine




Figure 8 SSH4 Baseboard layout

Downloaded from www.Manualslib.com manuals search engine

Table 4 SSH4 Baseboard Components

Key	Component	Key	Component
A	PCI bus 64 bit, 100 MHz, Hot Plug	T	Chassis Intrusion Detect connector (P36)
B	PCI bus 64 bit, 100 MHz, Non-Hot Plug	U	14-pin Power Control connector (P35)
C	PCI bus 32 bit, 33 MHz, Non-Hot Plug	V	24-pin Power connector (P32)
D	ICMB connector (P24)	W	20-pin Power connector (P28)
E	HPIB connector (P23)	X	Serial port B connector (P17)
F	Back Panel I/O connectors)	Y	USB #3 Header (P18)
G	Intel 82550 Ethernet controller	Z	Front Panel Header (P19)
H	ATI* Rage* XL 2D/3D graphics accelerator	AA	IDE Connector (P13)
J	Intel 82544 Ethernet controller	BB	SCSI LVD connectors (P4 and P7)
K	Video RAM (VRAM) (4 MB total)	CC	IPMB connector (P12)
L	Processor board connectors (P21 and P22)	DD	AIC7899 or AIC 7902 SCSI controller
M	ServerWorks South Bridge Controller (CSB5)	EE	Fan connector (P11)
N	BMC (Sahalee) component	FF	ServerWorks PCI-X Bus Bridge Controller (CIOB30)
P	BIOS Flash component	GG	ServerWorks PCI-X Bus Bridge Controller (CIOB30)
Q	PC87417 Super I/O controller	HH	RAID LED connectors (P1 and P2)
R	BMC Flash component	JJ	HSBP connector (P16)
S	Battery	KK	HSBP connector (P15)

The SSH4 memory subsystem consists of a single memory expansion board. This board supports up to 12 DDR registered ECC SDRAM memory modules. The SSH4 baseboard implementation in SPSH4 server supports both stacked and unstacked memory modules for up to 24 GB of system memory.

The SSH4 boardset provides the following features:


- Three interleaved memory banks.
- Four 184 pin DIMMS per bank.
- Banks must be populated in order.
- Single bit error correction – If a single-bit error is detected, the ECC logic generates a new Qword with a pattern that corresponds to the originally received 8-bit ECC parity code and returned to the requestor (the processor or the PCI master)
- Multi Bit error detection – Additional errors within the same Qword constitute a multibit error which may be unrecoverable. In the case of a multi-bit error, a non-maskable interrupt (NMI) is issued that instructs the system to shut down to avoid data corruption. (multibit errors are very rare).
- Memory Scrubbing – Error correction is performed on data being read from memory. The correction is the passed to the requestor and at the same time is “scrubbed” or corrected in

Downloaded from www.Manualslib.com manuals search engine

main memory. Memory scrubbing prevents the accumulation of single –bit errors in main memory tha would become unrecoverable mult-bit errors.

- Chipkill* - Chipkill is the ability of the memory system to wothstand a mult-bit failure within DRAM device, including a failure that causes incorrect data on all bits of the device.

Figure 9 SSH4 Memory Module



3.2 Guidelines For Installing Memory in the SSH4 Server Board.

- Install only memory modules validated with this particular board. Refer to the Tested Hardware and Operating System List and/or Http:// support.intel.com.
- Bank 1 must be populated with Dimms first. See figure 9 above.
- All four Dimms within a bank must be identical
- Baseboard Management Controller (BMC) providing monitoring, alerting, and logging of critical system information obtained from embedded sensors on baseboard
- 8 megabit Flash device for system BIOS
- Three externally accessible USB ports; two at rear bulkhead and one at front panel
- One IDE connector, supporting up to two ATA 66 compatible devices

Downloaded from www.Manualslib.com manuals search engine

4. Power supply Subsystem

This section defines the features and functionality of the SSI compliant 600 watt power supply, a universal input switching power supply. The power supplies are located in the power supply bay mounted near the rear of the chassis. The system may be configured either with two 600 W power supplies in a non-redundant configuration, or three 600 W power supplies for a redundant power (2 + 1) configuration. Each power supply requires an individual power cord. When the system is configured with three power supplies the following features are supported:

- The user can replace a failed power supply without interrupting system functionality under any loading condition.
- AC power to one of the power cords can be interrupted without loss of functionality.

Power from the power supply subsystem is carried to internal system boards and peripheral devices via discrete cables. Two 600 watt power supplies are capable of handling the worst case power requirements for a fully configured SPSH4 system. This includes four 75 watt Intel Xeon – MP processors, 24 GB of memory and ten hard drives at 20 watts per drive. Figure 8 shows the SPSH4 power supply.

Downloaded from www.Manualslib.com manuals search engine




Figure 8: SPSH4 Power supply

!WARNING!

The total power requirement for the SPSH4 server system exceeds the 240VA energy hazard limit that defines an operator accessible area. As a result, only qualified service personnel should access the processor, memory, and non-hot plug I/O areas on the system baseboard while the system is energized.

The following are the main features of the power supply subsystem:

- 1140 W output capability for two or three power supplies in full AC input voltage range
- Up to three 600 watt PFC power factor correcting power supplies for 2+1 power redundancy
- Power good indication LED
- Predictive failure warning LED
- Failure warning LED
- Internal cooling fans with multi-speed capability
- Remote sense of +3.3V, +5V, and +12V outputs
- AC_OK circuitry for brown out protection
- Built-in load sharing capability
- Built-in overloading protection capability
- On board field replaceable unit (FRU) information for each module
- I^2C interface for server management functions

Downloaded from www.Manualslib.com manuals search engine

- Integral handle for insertion/extraction
- Separate power cords for AC redundancy

The power supplies are populated in the chassis in a specific order as viewed from the rear of the server system. See Figure 9. For a rack configuration, the power supplies are installed from left to right. In a pedestal configuration the modules are installed from the bottom to the top. All of the power supplies implement blind mating connectors for easy installation. Each power supply implements two AC input fuses rated at 250V/15A, one for line and one neutral. Power supplies are not required to be on the same AC power phase. The power supply is held to the chassis frame with four 6-32 screws. These four screws and the AC cord must be removed to hot swap the power supply.



Figure 9: Rear view of SPSH4 Power Supply Bay

The power supply has four externally enabled outputs: +12V,+5V,+3.3V,-12V, and one +5VSB (standby) output. The +5VSB standby output is present whenever AC power is applied to any single power supply. The power supply has a minimum efficiency of 60% to its DC output pins at maximum load currents at rated nominal input voltages and frequencies.

Several LEDs on each power supply can be viewed from the rear of the server system. These indicate the power state for that particular module. Looking at the system from rear of the power supply, from left to right the LEDs are power, predictive fail, and fail.

Downloaded from www.Manualslib.com manuals search engine

- The power LED is green and blinks to indicate that AC is applied to the power supply and +5VSB standby output voltage is available. This LED will turn a solid green to indicate the power supply is on and all the power output voltages are available.
- The predictive fail LED blinks amber LED and indicates the power supply will fail in the near future due to a poorly performing fan.
- The fail LED is amber and indicates that the power supply has experienced a failure of some type.

When the power supply configuration changes, the SDR utility must be run so that server management will properly monitor the new configuration.

A power LED on the front panel, labeled PWR, is green when power is applied to the system. Table 3 describes the conditions of the LEDs for the power supply.

Table 3: LED Indicators

	Power supply LEDs		
Power supply Condition	**Power LED (green)**	**Predictive Fail LED (amber)**	**Fail LED (amber)**
No AC power to all PSU	OFF	OFF	OFF
No AC power to this PSU only	OFF	OFF	ON
AC present / Standby Outputs On	Blinking	OFF	OFF
Power supply DC outputs ON and OK	ON	OFF	OFF
Power supply failure	OFF	OFF	ON
Current limit	ON	OFF	Blinking
Predictive failure	ON	Blinking/Latched	OFF

4.1 Mechanical Dimensions

Mechanical drawings and dimensions, in millimeters, for the power supply are shown in the Figure 10 below. The power supply has a handle that pivots to assist insertion and extraction and provides retention.

Downloaded from www.Manualslib.com manuals search engine




Figure 10: SPSH4 Power supply Outline Drawing

Downloaded from www.Manualslib.com manuals search engine

4.2 Airflow Requirements

Airflow enters the power supply at the DC connector face and is exhausted at the handle face. Fan speed is controlled by the server system via the FANC signal to the power supply. The power supply may override the FANC signal and operate the fan at HIGH speed if the conditions of the power supply exceed those specified in Table 4. The minimum airflow required by the power supply for high and low intake temperatures are shown in Table 4 also.

Table 4: Airflow Requirements

Item	Description	Minimum CFM
High Ambient Temperature	Airflow through power supply; max load, T_{intake}=50°C, 5000 ft elevation	21
Low Ambient Temperature	Airflow through power supply; max load, T_{intake}=35°C, 5000 ft elevation	17

4.2.1 Over-Temperature Protection

The power supply is protected against over temperature conditions caused by loss of fan cooling or excessive ambient temperature. In the event of an OTP condition, the power supply is shutdown. When the power supply temperature returns to within specified limits, the power supply will automatically restore power.

The power supply sends an alert to the system of the OTP condition via the power supply FAIL signal and the amber FAIL LED at the rear of the failed power supply is illuminated. When temperatures read by the over temperature sensors in power supply return to within the normal operating range, DC power is automatically restored. The power supply has built in hysteresis circuits to prevent the power supply from oscillating on and off due to over temperature recovery conditions.

4.2.2 Connectors and Pinouts

4.2.2.1 AC Inlet

The power supply AC inlet is an IEC320 C-14 receptacle. The AC power pins and wiring prior to the protective fuse(s) have a peak current rating higher than the peak inrush current or maximum fault current drawn by the power subsystem. The safety ground pin of the power supply is the first pin to connect and the last to disconnect when the AC cord is inserted or removed from the power subsystem housing.

4.2.2.2 DC Output Connector

The blind-mate DC output connector is the interface to the server system for output voltages, control signals, and alarm signals. Connector pin descriptions and assignments are listed in Table 5 and Table 6. Pin A6 is shortened to disabling power supply just prior to disconnecting the DC output connector during a hot swap operation. The connector is keyed to the power supply by the positioning of the guide/keying pins on either side of the connector. The keying location for the connector is A1.

Downloaded from www.Manualslib.com manuals search engine

Table 5: Signal Descriptions

Signal	Description	Signal	Description	Signal	Description
12LS	12V load share bus	PWOK	Power OK output	5VSB	5V standby output
5LS	5V load share bus	ACOK#	AC OK output	-12 V	-12V output
3.3LS	3.3V load share bus	ACRange	AC input range select	SCL	I^2C Clock signal
12VS	12V remote sense	PSKILL	Supply fast shutdown	SDA	I^2C Data signal
5VS	5V remote sense	FAIL	Failure signal	A0	I^2C address bit 0
3.3VS	3.3V remote sense	PRFL	Predictive failure signal	A1	I^2C address bit 1
ReturnS	Return remote sense	PRESENT#	Power supply present	FANC	Fan control signal
PSON#	Power enable input				

Note:

ACOK and AC-Range are reserved for use internal to the power supply.

Table 6: Output Connector Pin-out

Signal Pins						
	1	2	3	4	5	6
D	12LS	PWOK	ACOK#	ACRange	ReturnS	-12 V
C	A0	SCL	FAIL	PRFL	12VS	3.3VSB [1]
B	A1	SDA	3.3VS	5VS	Reserved	+5VSB
A	3.3LS	PRESENT#	FANC	5LS	PSON#	PSKILL

Power Blades										
P1	P2	P3	P4	P5	P6	P7	P8	P9	P10	P11
+12V	+12V	GND	GND	GND	GND	GND	+5 V	+5 V	+3.3V	+3.3V

Notes:

1 The 3.3VSB output is an optional output.

Signals defined as low true use the following convention: signal# = low true




Figure 11: Connector Pin Locations

Downloaded from www.Manualslib.com manuals search engine

4.2.3 AC Electrical Specifications

4.2.3.1 AC / DC Supply Redundancy

The power sub-system has three AC inlets, one for each power supply. Each power supply does not rely on other modules for any functionality except for load sharing. AC input to the power supply is fully isolated. Therefore, it is not subject to AC phase differential issues. All DC outputs have a device to isolate the power supply from the main system power during a power supply failure or during a hot swap operation. The SPSH4 server system has power redundancy for any DC load condition in a 2+1 power supply configuration.

4.2.3.2 AC Input Voltage Ranges

The power supply incorporates universal power input with active power factor correction, which reduces line harmonics in accordance with the EN61000-3-2 and JEIDA MITI standards. The power supply operates within all specified limits over the input voltage range specified in Table 7. Harmonic distortion of up to 10% THD will not cause the power supply to go out of specified limits. The power supply has a minimum efficiency of 60% to the DC output pins at maximum load currents, at rated nominal input voltages and frequencies.

Table 7: AC Input Voltage Rating

Parameter	Minimum	Rated	Maximum	Max Input Current (600W)
Voltage (110)	90 V_{rms}	100-127 V_{rms}	132 V_{rms}	12 A_{rms}
Voltage (220)	180 V_{rms}	200-240 V_{rms}	264 V_{rms}	6 A_{rms}
Frequency	47 Hz	50/60 Hz	63 Hz	-

4.2.3.3 AC Line Dropout and Hold-up Time

An AC line dropout is defined as when the AC input drops to 0VAC for one cycle or less during any phase of the AC line. During an AC dropout, the power supply meets the dynamic voltage regulation requirements over the rated load. Dynamic voltage regulation requirements may be seen in Table 20.

An AC line dropout will not cause any tripping of control signals or protection circuits. If the AC dropout lasts longer than one cycle then the power supply may shutdown but will recover and meet all turn on requirements. The power supply meets the AC dropout requirements over all rated AC voltages, frequencies, and output loading conditions. Any dropout of the AC line will not cause damage to the power supply.

4.2.3.4 AC Line Transient Specification

AC line transient conditions are defined as “sag” and “surge” conditions. The sag conditions are also commonly referred to as “brownout”. The sag condition is defined as the AC line voltage dropping below nominal voltage. The surge conditions are defined as when the AC line voltage rises above nominal voltage. The power supply meets the performance requirements under the AC line sag and surge conditions shown in Table 8 and Table 9, respectively.

Downloaded from www.Manualslib.com manuals search engine

Table 8: AC Line Sag Transient Performance

Duration	Sag	Operating AC Voltage	Line Frequency	Performance Criteria
Continuous	10%	100VAC-127VAC 200VAC-240VAC	50/60Hz	No loss of function or performance
0 to 1 AC cycle	100%	100VAC-127VAC 200VAC-240VAC	50/60Hz	No loss of function or performance
> 1 AC cycle	>10%	No loss of function or performance	50/60Hz	Loss of function acceptable, self recoverable

Table 9: AC Line Surge Transient Performance

Duration	Surge	Operating AC Voltage	Line Frequency	Performance Criteria
Continuous	10%	100VAC-120VAC 200VAC-240VAC	50/60Hz	No loss of function or performance.
0 to ½ cycle	30%	110VAC, 220VAC	50/60Hz	No loss of function or performance.

4.2.3.5 Susceptibility

The power supply complies with the limits defined in EN50082-2 while maintaining normal performance within the specification limits.

Table 10: Electrostatic Discharge, IEC 801-2/IEC 1000-4-2

Level	Test Voltage, Contact Discharge	Test Voltage, Air Discharge
3	8Kv	15Kv

Table 11: Electrical Fast Transient/Burst, IEC 801-4/IEC 1000-4-4

Level	AC Inlet
3	1Kv

Table 12: Radiated Immunity, IEC 801-3/IEC1000-4-3

Field Strength	Frequency Range	Step Size	Modulation
5V/meter	26MHz to 500MHz	1% of previous frequency	None

4.2.3.6 Surge Immunity

In addition to complying with EN50082-2 for Surge immunity, the product must also comply with ANSI C62.45-1992. The requirements of the Intel *Environmental & Reliability Board and System*

Downloaded from www.Manualslib.com manuals search engine

Validation Test Handbook for surge withstand capability indicates the test methods and levels used during Intel system qualification testing, which are derived from these standards.

Table 13: Surge Immunity IEC 1000-4-5

Level	Open Circuit Voltage	Minimum time between Surges
3	2.0Kv ± 10%	20 sec

Table 14: Ring Wave

Open Circuit Voltage	Minimum time between Surges
3.0Kv ± 10%	20 sec

4.2.3.7 AC Line Fast Transient Response

The power supply meets the *EN61000-4-5* directive and any additional requirements in *IEC1000-4-5: 1995* and the Level 3 requirements for surge-withstand capability.

Downloaded from www.Manualslib.com manuals search engine

4.2.3.8 AC Line Inrush

AC line inrush current does not exceed 25A peak for quarter of the AC cycle. The inrush current must not exceed the I^2t curve shown in Figure 12. The inrush current must not exceed 100A peak for any duration of time.

The power supply meets the inrush requirements for any rated AC voltage, during turn on at any phase of AC voltage, during hot plug, during any AC dropout condition, over the specified temperature range, and during AC power cycling.




Figure 12: Inrush Curve

4.2.3.9 Dielectric Strength Requirements

The power supply meets all safety agency requirements for dielectric strength.

4.2.3.10 AC Line Fuse

Each power supply has two line fuses, one for each side of the AC input. AC line-fusing meets all safety agency requirements.

4.2.3.11 AC Inlet Connector

The AC input connector is an IEC 320 C-14 power inlet. This inlet is rated for 15A / 250VAC.

4.2.4 DC Output Specification

The SPSH4 server system runs with either two or three power supplys installed. The power supplys operate with their outputs directly paralleled. The power supplys equally share the total load currents within the limits specified. Equal power sharing of paralleled power supplys is required to prevent life shortening stress concentration in individual power supplys. Power sharing is accomplished by actively matching the output currents on the high power outputs. The current sharing load deviation is defined as follows:

```
Load_Deviation = [(Actual_Load – Mean_ Load)/(Mean Load)] * 100%
```


Downloaded from www.Manualslib.com manuals search engine

Steady state DC output voltages at the remote sense points always remain within the limits specified by Table 15 for all combinations of operating line, load, load transient, and environment specified herein.

Table 15: DC Output Voltage Limits

Parameter	Minimum	Nominal	Maximum	Units	Tolerance
+3.3V	+ 3.25	+ 3.30	+ 3.35	V	± 1.5%
+5V	+ 4.90	+5.00	+ 5.10	V	± 2%
+12V	+ 11.76	+12.00	+ 12.24	V	± 2%
-12V	- 13.08	-12.00	- 11.40	V	+ 9% and -5%
+5V Standby1	+ 4.85	+5.00	+ 5.20	V	+ 4% and -3%

Note:

1 +5V standby is in reference to the common remote sense returning potential.

Downloaded from www.Manualslib.com manuals search engine

4.2.4.1 DC Output Rating

The power supply meets the static regulation requirements under the loading conditions specified in Table 16. The combined continuous output load applied to the power supply will not exceed 600 W. If the power exceeds 600 W, the power supply should not be subjected to this maximum current draw for more than 12 seconds.

Table 16: 600W Load Ratings

Voltage	Single Power supply Maximum Output Current		
	Minimum Continuous	Maximum Continuous	Peak
+3.3V	1 A	40 A	
+5V	1 A	34 A	
+12V	0 A	36 A	42 A
-12V	0 A	1.0 A	
+5V Standby	0 A	2 A	

The total system maximum load condition is shown in Table 17. Either two or three power supplys can support the total system maximum load.

Table 17: Total System Load at Line AC Input

Voltage	Total System Maximum Load Condition		
	Minimum Continuous	Maximum Continuous	Peak
+3.3V	1.5 A	76 A	
+5V	1.5 A	64.6 A	
+12V	1.5 A	68.4 A	79.8A
-12V	0.0 A	1.0 A	
+5V Standby	0.0 A	2.0 A	

Table 18: Absolute Worst Case System Power Budget

Subsystem	Qty	+5V	+3.3V	+12V	-12V	+5VSB	Total (W)
Board Set	1	4.36	10.76	1.15	0.01	0.38	73.13
CPU	4			30.85			370.20
DDR DRAM	12		1.97	6.10			79.70
FAN	6			6.32			75.84
HDD	10	11.00		9.00			163.00
CD-ROM	1	0.40		0.70			10.40
FDD	1	0.24					1.20
5½" Device	2	1.54		0.80			17.30
PCI-X (64bit/100MHz)	6	9.00	13.64			0.31	91.56

Downloaded from www.Manualslib.com manuals search engine

Subsystem	Qty	+5V	+3.3V	+12V	-12V	+5VSB	Total (W)
PCI (32bit/33MHz)	2	6.00				0.03	30.15
System Total		32.54	26.37	54.92	0.01	0.72	912.48
Power Subsystem Spec		64.60	76.00	68.40	1.00	2.00	1140.00
Margin		32.06	49.63	13.48	0.99	1.28	227.52

4.2.4.2 Remote Sense

The power supply has remote sense return (ReturnS) to regulate out ground drops for all output voltages (+3.3V, +5V, +12V, -12V and +5VSB). The power supply operates within the specification shown in Table 19 over the full range of voltage drops from the power supply's output connector to the remote sense points on the server system boardset.

Table 19: Remote Sense Drops

Output	Max Drops	Units
+3.3V	250	mV
+5V	250	mV
+12V	500	mV
Remote Sense return	100	mV

4.2.4.3 DC and Transient Load Output Voltage Limit

The power supply will maintain regulation specified in Table 20 under all specified conditions, including parallel operation with other power supplys, line variations, load variations, transient load conditions, peak ripple/noise, maximum remote sense drops, subsystem hot swap, and temperature change. The +3.3V, +5V, and +12V output voltages should be measured at their respective remote sense points. The output voltages must stay within regulation requirements with the remote sense regulating out the maximum drops shown in Table 19.

Table 20: Dynamic Tolerance Requirement

Output	Min. Output [V]	Max. Output [V]	Tolerance
+3.3V	3.20	3.43	+4% & -3 %
+5V	4.85	5.20	+4% & -3 %
-12V	11.4	13.08	+9 & -5%
+12V	11.64	12.48	+4% & -3 %
+5V standby	4.85	5.20	+4% & -3 %

Downloaded from www.Manualslib.com manuals search engine

4.2.4.4 Ripple and Noise

The maximum allowed ripple/noise output of the power supply is defined in Table 21. This is measured over a bandwidth of 0Hz to 20MHz at the power supply output connector. A 10μF tantalum capacitor in parallel with a 0.1μF ceramic capacitor are placed at the point of measurement. The test setup is shown in Figure 13.




Figure 13: Differential Noise Test Setup

Table 21: Ripple and Noise

Voltage	Ripple / Noise pk-pk	Ripple/Noise pk-pk
+3.3V	1.5%	50 mV
+5V	1%	50 mV
+12V	1%	120 mV
-12V	1%	120 mV
+5V Standby	1%	50 mV

Downloaded from www.Manualslib.com manuals search engine

4.2.4.5 Power Timing

Power timing refers to the timing requirements for single power supply operation. The output voltages must rise from 10% to within regulation limits (T_{vout_rise}) within 5 to 200ms. The +3.3V, +5V and +12V output voltages should start to rise approximately at the same time. All outputs must rise monotonically. The +5V output needs to be greater than the +3.3V output during any point of the voltage rise, however, never by more than 2.25V.

Each output voltage reaches regulation within 100ms (T_{vout_on}) of each other and begin to turn off within 100ms (T_{vout_on}) of each other. Figure 14 shows the timing requirements for a single power supply being turned on and off via the AC input, with PSON held low and the PSON signal, with the AC input applied. The ACOK# signal is not being used to enable the turn on timing of the power supply.

Table 22: Output Voltage Timing

Item	Description	Min	Max	Units
T_{vout_rise}	Output voltage rise time from each main output.	5	200	msec
T_{vout_off}	All main outputs must be within regulation of each other within this time.		300	msec
T_{vout_on}	All main outputs must be within regulation of each other within this time.		100	msec




Figure 14: Output Voltage Timing

Table 23: Turn On/Off Timing

Downloaded from www.Manualslib.com manuals search engine

Item	Description	Min	Max	Units
$T_{sb_on_delay}$	Delay from AC being applied to 5VSB being within regulation.		1500	msec
$T_{ac_on_delay}$	Delay from AC being applied to all output voltages being within regulation.		2500	msec
T_{vout_holdup}	Time all output voltages, including 5VSB, stay within regulation after loss of AC.	21		msec
T_{pwok_holdup}	Delay from loss of AC to deassertion of PWOK	20		msec
$T_{pson_on_delay}$	Delay from PSON# active to output voltages within regulation limits.	5	400	Msec
T_{pson_pwok}	Delay from PSON# deactive to PWOK being deasserted.		50	Msec
T_{acok_delay}	Delay from loss of AC input to deassertion of ACOK#.	20		Msec
T_{pwok_on}	Delay from output voltages within regulation limits to PWOK asserted at turn on.	100	1000	Msec
T_{pwok_off}	Delay from PWOK deasserted to output voltages (3.3V, 5V, 12V, -12V, 5VSB) dropping out of regulation limits.	1		Msec
T_{pwok_low}	Duration of PWOK being in the deasserted state during an off/on cycle using AC or the PSON signal.	100		Msec
T_{sb_vout}	Delay from 5VSB being in regulation to 5V being in regulation at AC turn on.	50	1000	Msec




Figure 15: Turn On/Off Timing

Downloaded from www.Manualslib.com manuals search engine

4.2.5 Electrical Protection Circuits

Protection circuits inside the power supply will cause only the power supply's main outputs to shutdown during either an over-voltage or over-current condition. The 5VSB output remains powered on if the failure does not involve this output. When a protection circuit shuts down the power supply, both the FAIL LED and the FAIL signal will be activated.

4.2.5.1 Over-Voltage Protection

Over-voltage protection is sensed inside the power supply. The power supply will shutdown and latch off following an over-voltage condition. This latch can be cleared by toggling the power supply PSON# signal or by an AC power interruption of greater than 1 second. This over-voltage limit applies to all specified AC input voltages and output load conditions. Table 24 contains the over-voltage limits. The values are measured at the output of the power supply DC connector.

Table 24: Over-Voltage Limits

Output Voltage	Protection Point [V]
+3.3 V	3.8 – 4.5
+5 V	5.6 – 6.5
+12 V	13 – 14.5

4.2.5.2 Over- Current Protection

The power supply has over-current protection on +3.3V, +5V, and +12V outputs. The current limiting is of the voltage fold-back type. The over-current limit levels specified in Table 25 are maintained for a period of 2.6-second minimum and 3.6-second maximum. After this time the power supply will latch off. The power supply cannot be damaged from repeated power cycling in this condition.

Table 25: Over Current Protection Limits

Voltage	Over-current Limit
+3.3V	44.0 A minimum; 60.0 A maximum
+5V	37.4 A minimum; 51.0 A maximum
+12V	39.6 A minimum; 54.0 A maximum

Note:
Limits specified are per 600W power supply.

Downloaded from www.Manualslib.com manuals search engine

4.2.6 Control Signals

4.2.6.1 PSON

The PSON# signal is required to remotely turn on/off the power supply. PSON# is an active low signal that turns on the 3.3V, 5V, 12V, and -12V power rails. When this signal is not pulled low by the system, or if it is left open, the outputs (except the 5VSB) turn off. This signal is pulled to a standby voltage by a pull-up resistor internal to the power supply. See Figure 15 for the timing diagram.

Table 26: PSON Signal Characteristic

Signal Type	Accepts an open collector/drain input from the system. Pull-up to VSB located in power supply.	
PSON# = Low, PSKILL = Low	ON	
PSON# = Open, PSKILL = Low or Open	OFF	
PSON# = Low, PSKILL = Open	OFF	
	MIN	MAX
Logic level low (power supply ON)	0V	1.0V
Logic level high (power supply OFF)	2.0V	5.25V
Source current, Vpson = low		4ma
Power up delay: $T_{pson_on_delay}$	5msec	400msec
Power down delay: $T_{pson_off_delay}$	1.1msec	
PWOK delay: T_{pson_pwok}		50msec

4.2.6.2 PWOK

PWOK is a power good signal and will be pulled HIGH by the power supply to indicate that all the outputs are within the regulation limits of the power supply. When any output voltage falls below regulation limits or when AC power has been removed for a time sufficiently long so that power supply operation is no longer guaranteed, PWOK will be de-asserted to a LOW state. See Figure 15 for a representation of the timing characteristics of PWOK. The start of the PWOK delay time is inhibited as long as any power supply output is in current limit.

Table 27: PWOK Signal Characteristics

Signal Type	Open collector/drain output from power supply. Pull-up to VSB located power supply.	
PWOK = High	Power Good	
PWOK = Low	Power Not Good	
	MIN	MAX
Logic level low voltage, Isink=4mA	0V	0.4V
Logic level high voltage, Isource=200µA	2.4V	5.25V
Sink current, PWOK = low		4mA
Source current, PWOK = high		2mA
PWOK delay: T_{pwok_on}	100ms	1000ms
PWOK rise and fall time		100µsec
Power down delay: T_{pwok_off}	1ms	200mSec

Downloaded from www.Manualslib.com manuals search engine

4.2.6.3 PSKILL Signal

The PSKILL pin allows for hot swapping of the power supply. The PSKILL pin on the power supply is shorter than the other signal pins. When a power supply is operating in parallel with other power supplys and then extracted from the system, the PSKILL pin will quickly turn off the power supply and prevent arching of the DC output contacts. T_{PSKILL} (shown in Table 28) is the minimum time delay from when PSKILL pin unmates to when the power supply shuts down all power outputs.

When the PSKILL signal pin is not pulled down or left opened (for example when the power supply is being extracting from the system), the power supply will shut down regardless of the condition of the PSON# signal. The mating pin of this signal in the system is tied to ground. Internal to the power supply, the PSKILL pin is connected to a standby voltage through a pull-up resistor. Upon receiving a LOW state signal at the PSKill pin, the power supply will be allowed to turn on via the PSON# signal. Logic LOW on this pin by itself will not turn on the power outputs.

Table 28: PSKILL Signal Characteristics

Signal Type (Input Signal to Supply)	**Accepts a ground input from the system. Pull-up to VSB located in the power supply.**	
PSKILL = Low, PSON# = Low	ON	
PSKILL = Open, PSON# = Low or Open	OFF	
PSKILL = Low, PSON# = Open	OFF	
	MIN	MAX
Logic level low (power supply ON)	0V	1.0V
Logic level high (power supply OFF)	2.0V	5.25V
Source current, Vpskill = low		4ma
Delay from PSKILL=High to power supply turned off (T_{PSKill})[1]		100μsec

Note:

T_{PSKill} is the time from the PSKill signal deasserting HIGH to the power supply's output inductor

Downloaded from www.Manualslib.com manuals search engine

4.2.6.4 Power supply Failure

In the event of a power supply failure (OVP at any output, UV at any output, fan failure, or other failure) the power supply failure signal is allowed to go HIGH by the power supply.

Table 29: FAIL Signal Characteristics

Signal Type	Open collector/drain output from power supply. Pull-up to VSB located system.	
FAIL = High	Failed	
FAIL = Low	OK	
	MIN	MAX
Logic level low voltage, Isink=4ma	0V	0.4V
Logic level high voltage, Isink=50µA		5.25V
Sink current, FAIL = low		4ma
Sink current, FAIL = high		50µA
FAIL rise and fall time		100µsec

4.2.6.5 Predictive Failure Signal

This signal indicates that the power supply (or power supply fan) is reaching its end of life. The signal indicates a predictive failure when HIGH.

Table 30: PRFL Signal Characteristics

Signal Type (Active Low)	Open collector/drain output from power supply. Pull-up to VSB located in system.	
PRFL = High	Failing	
PRFL = Low	OK	
	MIN	MAX
Logic level low voltage, Isink=4mA	0V	0.4V
Logic level high voltage, Isink=50µA		5.25V
Sink current, FAIL = low		4mA
Sink current, FAIL = high		50µA
PRFL rise and fall time		100µsec

Downloaded from www.Manualslib.com manuals search engine

4.2.6.6 Power supply Present Indicator

The PRESENT# signal is used to sense the number of power supplys in the system (operational or not). This signal is connected to the power supply's output ground.

Table 31: PRESENT# Signal Characteristics

Signal Type	Output from power supply that is connected to ground. Pull-up to VSB located in system.	
PRESENT# = Low	Present	
PRESENT# = High	Not Present	
	MIN	MAX
Logic level low voltage, Isink=4mA	0V	0.4V
Logic level high voltage, Isink=50μA		5.25V
Sink current, PRESENT# = low		4mA
Sink current, PRESENT# = high		50μA

4.2.6.7 Power supply Fan Control

The power supply fan speed is controlled by the FANC signal. The fan speed (even during sleep mode) is controlled by a variable voltage on this pin. This signal allows the system to request control of the power supply fan. The control circuit in the system supplies voltage to this pin from 12V to 0V for the fan control request. If the FANC signal is left open the fan control defaults to power supply control.

Table 32: Fan Speed Control

Signal Type	Accepts an input voltage from the system. Pull-up to 12V located in power supply.	
FANC < 1V	Fan in SLEEP mode[1]	
2V < FANC < 3V	Fan in LOW speed[1]	
3V < FANC < 10.5V	Fan ramps from LOW to HIGH speed [1]	
FANC > 10.5V	Fan in HIGH speed[1]	
	MIN	MAX
Source current		2mA
Fan SLEEP mode output power [2]		50W
Fan LOW speed ambient temperature		35°C

Notes

1. This is a request from the system to the power supply to operate the fan at this condition. The power supply can over ride this request and increase the fan speed if the power supply requires more cooling. See note 2 for fan SLEEP mode requirements.
2. When the power supply fan is in SLEEP mode the fan must be operating at its minimum RPM, which is slow enough to not output any noticeable audible levels. The power supply must be able to supply 0W to 50W of output power at 50°C ambient (any combinations of 3.3V, 5V, and 12V output currents) in the power supply fan SLEEP mode condition without the power supply over riding and turning the fan to LOW or HIGH speed.

Downloaded from www.Manualslib.com manuals search engine

4.2.6.8 Power supply Field Replacement Unit (FRU) Signals

The FRU data format is compliant with the *Intelligent Platform Management Interface (IPMI) Specification 1.5*. The current version of these specifications is available at http://developer.intel.com/design/servers/ipmi/spec.htm

Four pins are allocated for the FRU information on the power supply connector. One pin is the Serial Clock (SCL). The second pin is used for Serial Data (SDA). Pins three and four are address lines A0 and A1 to indicate to the power supply's EEPROM which position the power supply is located in the server system.

Table 33: Pins for Power supply Connector FRU Information

A0	A1	Address
Low	Low	0xA0
Low	High	0xA2
High	Low	0xA5
High	High	0xA6

The FRU circuits inside the power supply are powered off of 5VSB on the system side of the or'ing device and grounded to ReturnS (remote sense return). The Write Control (or Write protect) pin is tied to ReturnS inside the power supply so that server management can write to the EEPROM.

Downloaded from www.Manualslib.com manuals search engine

4.3 Cooling Subsystem

Main system components are cooled by a set of fans mounted in a fan bay near the front of the chassis and in front of the E-bay. The fan bay is shown below.




Figure 16: Fan Bay (Shown with all Fan Banks Installed)

The SPSH4 system comes in a redundant four-fan bank configuration consisting of two 120mm fan banks for cooling the processor section of E-bay and two 80mm fan for cooling PCI section of E-bay. The fans blind mate connect to the system fan board. Only a minimal configuration is supported in the two fan bank configuration (one 120mm fan bank plus one 80mm fan):

- One processor
- Four memory DIMMs

Note: Since SCSI bay hard drives and 5¼" peripheral bays are not cooled by dedicated SCSI bay fans and from power supply fans, they are not subject to any limitations from the two-fan bank configuration described above.

The four-fan bank configuration supports any system configuration. Air flows through the fan bay and then through E-bay, and exhausts through the rear panel of the system. Additionally, both SCSI bay fans and power supply fans pull air from the SCSI bays and from the 5¼" peripheral bay. Each fan provides tachometer signal output to server management to indicate a fan failure. Each fan also provides a presence signal to the fan board to indicate a missing fan.

4.3.1 Redundancy and Ambient Temperature Control

The fan board contains a pulse-width-modulation (PWM) circuit, which cycles the +12 V fan voltage to provide quiet operation when system ambient temperature is low, and there are no fan failures. Under normal room ambient conditions (less than 30°C) the fan power control

Downloaded from www.Manualslib.com manuals search engine

circuit operates the fans at low speed. When ambient temperature is between 30°C and 35°C or a fan fails, the fan power control circuit operates the fans at maximum speed.

4.3.2 Cooling Summary

The redundant, six fan cooling subsystem is sized to provide cooling for:

- Up to four Intel MP Xeon processors dissipating 75 W each
- 24 GB of DDR memory
- Ten 15k RPM hard drives
- Eight full-length PCI cards
- Three 5¼“ peripheral bay devices
- DC output redundant, fully-loaded power subsystem

The cooling subsystem is designed using a worst-case analysis with no margin under a single fan failure condition. The lower fan speed settings were chosen to meet acoustic and thermal requirements. To ensure that all components remain within specification under all system environmental conditions, there will be a recommended time limit for fan and power supply module hot-swap operations.

Downloaded from www.Manualslib.com manuals search engine

5. Cables and Connectors

This chapter describes interconnections between the various components of the SPSH4 system. This chapter includes an overview diagram of the SPSH4 server system interconnections. Refer to the appropriate board *External Product Specification* for other connector signal descriptions and pin-outs.

5.1 Interconnect Block Diagram

Figure 17 shows interconnections for all of the boards used in the SPSH4 server system.




Figure 17: SPSH4 System Interconnect Block Diagram

Downloaded from www.Manualslib.com manuals search engine

5.2 Cable and Interconnect Descriptions

Table 34 describes all cables and connectors of SPSH4 server system.

Table 34: System Interconnect Descriptions

Type	Qty	From	To	Interconnect Description
32bit PCI	2	SSH4 baseboard	PCI adapter card	120pin card edge connect
64bit PCI-X, 3.3V	6	SSH4 baseboard	PCI-X adapter card	184pin card edge connect
Keyboard	1	SSH4 baseboard	External interface	PS2 keyboard device
Mouse	1	SSH4 baseboard	External interface	PS2 mouse device
System Control	1	SSH4 baseboard	Front panel board	2x17 flat ribbon cable
Floppy	1	SSH4 baseboard	Floppy device	2x17 flat ribbon cable
IDE	1	SSH4 baseboard	CD-ROM device	2x20 flat ribbon cable
HPIB	1	SSH4 baseboard	HPIB board	2x14 flat ribbon cable
Parallel port	1	SSH4 baseboard	External interface	25pin parallel port connector
Serial port A	1	SSH4 baseboard	External interface	9pin serial port connector
100/10 Ethernet	1	SSH4 baseboard	External interface	RJ45 connector port
1000/100/10 Ethernet	1	SSH4 baseboard	External interface	10-pin connector port
Internal Wide Ultra-160 or U320 Scsi , Channel A	1	SSH4 baseboard	SCSI bay HDD backplane	68-pin solid core twisted pair ribbon cable
External Wide Ultra-160 or U320 SCSI, Channel B	1	SSH4 baseboard	SCSI bay HDD backplane or 5¼" Device	68-pin solid core twisted pair ribbon cable
Aux IMB	1	SSH4 baseboard	SCSI bay HDD backplane	1x4-pin connector on baseboard discrete cabled to a 1x4 pin connector on SCSI bay HDD backplane
ICMB internal	1	SSH4 baseboard	ICMB board	1x5-pin cable
ICMB external	2	ICMB board	External interface	1x6-pin ICMB cable
USB	2	SSH4 baseboard	External interface	1x4-pin USB cables
Video	1	SSH4 baseboard	External interface	15-pin monitor device
Main power 1	1	PDB	SSH4 baseboard	2x10-pin discrete cable
Main power 2	1	PDB	SSH4 baseboard	2x12-pin discrete cable
Aux power	1	PDB	SSH4 baseboard	2x7-pin discrete cable
FP serial port B internal	1	SSH4 baseboard	Front panel board	2x5 round cable
FP USB 3 internal	1	SSH4 baseboard	Front panel board	2x5 sheilded round cable
Processor Board	2	SSH4 baseboard	SSH4 processor board	6x24-pin HDM connect
Processor	4	SSH4 processor board	Intel® Xeon™ processor	603-pin ZIF BGA socket
Memory	1	SSH4 baseboard	SSH4 memory module	330-pin card edge connect

Downloaded from www.Manualslib.com manuals search engine


Type	Qty	From	To	Interconnect Description
DIMM	12	SSH4 memory module	DIMM	168-pin card edge connect
SCA-2 HDD	5	SCSI bay HDD backplane	External Interface	80-pin SCA-2 compatible device
SAFE-TE	1	SCSI bay HDD backplane	SAF-TE board	120-pin card edge connect
HDD power	2	PDB	SCSI bay HDD Backplane	1x4-pin discrete cable
92mm SCSI bay fan	1	SCSI bay HDD backplane	92mm fan	1x3-pin discrete cable
USB 3	1	Front panel	External Interface	1x4-pin USB cables
Serial port B	1	Front panel	External Interface	8-pin RJ45 cable
Fan power	1	PDB	Fan board	2x3-pin discrete cable
120mm system fan bank	2	Fan board	120mm fan bank	2x5-pin blind mate connector
80mm system fan	2	Fan board	80mm fan	2x2-pin blind mate connector
Peripheral power	4	PDB	Floppy or 5¼" device	1x4-pin connectors
AC Power	2	Power supply	External interface	Recommend 3pin SJT power cord

5.3 Operator-Accessible Interconnects

5.3.1 Keyboard and Mouse Ports

These identical PS/2 compatible ports share a common housing.

Table 35: Keyboard and Mouse Ports

Mouse		Keyboard or Mouse Connector	Keyboard	
Pin	Signal		Pin	Signal
1	MSEDAT (mouse data)		1	KEYDAT (keyboard data)
2	No connection		2	No connection
3	GND		3	GND
4	Fused VCC (+5 V)		4	Fused VCC (+5 V)
5	MSECLK (mouse clock)		5	KEYCLK (keyboard clock)
6	No connection		6	No connection

Downloaded from www.Manualslib.com manuals search engine

5.3.2 Serial Ports

The baseboard provides two RS-232C serial ports (Serial A is at the rear panel of the system, Serial B is either at a knockout at the rear panel or defaults to the front panel). Serial A is a D-subminiature 9-pin connector. Serial B is an RJ45 8-pin connector on the front panel or it is a D-subminiature 9-pin connector at the rear panel of the system. Each serial port can be enabled separately with the configuration control provided on the baseboard.

Serial B port can be used either as an Emergency Management Port (EMP) or as a serial port. As an Emergency Management Port, serial B port is used as a communication path by the server management RS-232 connection to the Front Panel Controller. This provides a level of emergency management through an external modem. The RS-232 connection can be monitored by the Front Panel Controller when the system is in a powered down (standby) state. Additional information can be found in the *Emergency Management Port Interface External Product Specification*.

Table 36: Serial Port A Connector


Pin	Signal	Serial Port A Connector
1	DCD (carrier detect)	
2	RXD (receive data)	
3	TXD (transmit data)	
4	DTR (data terminal ready)	
5	GND	
6	DSR (data set ready)	
7	RTS (request to send)	
8	CTS (clear to send)	
9	RIA (ring indicator)	

Downloaded from www.Manualslib.com manuals search engine

5.3.3 Parallel Port

The IEEE 1284-compatible parallel port, used primarily for a printer, sends data in parallel format. The parallel port is accessed through a D-subminiature 25-pin connector.

Table 37: Parallel Port Connector


Pin	Signal	Parallel Port Connector	Pin	Signal
1	STROBE_L		14	AUFDXT_L (auto feed)
2	Data bit 0		15	ERROR_L
3	Data bit 1		16	INIT_L (initialize printer)
4	Data bit 2		17	SLCTIN_L (select input)
5	Data bit 3		18	GND
6	Data bit 4		19	GND
7	Data bit 5		20	GND
8	Data bit 6		21	GND
9	Data bit 7		22	GND
10	ACK_L (acknowledge)		23	GND
11	BUSY		24	GND
12	PE (paper end)		25	GND
13	SLCT (select)			

Downloaded from www.Manualslib.com manuals search engine

5.3.4 Video Port

The video port interface is a standard VGA compatible 15-pin connector. On-board video is supplied by a ATI RAGE XL video controller with 4 MB of on-board video SGRAM.


Table 38: Video Connector

Pin	Signal	Video Connector
1	Red (analog color signal R)	
2	Green (analog color signal G)	
3	Blue (analog color signal B)	
4	No connection	
5	GND	
6	GND	
7	GND	
8	GND	
9	Fused VCC (+5V)	
10	GND	
11	No connection	
12	DDCDAT	
13	HSYNC (horizontal sync)	
14	VSYNC (vertical sync)	
15	DDCCLK	

5.3.5 Universal Serial Bus (USB) Interface

The baseboard provides two stacked USB ports (Port 0 on the top, Port 1 on the bottom). The built-in USB ports permit the direct connection of two USB peripherals without an external hub. If more devices are required, an external hub can be connected to either of the built-in ports.

Table 39: Dual USB Connector

Pin	Signal	Dual USB Connector
A1	Fused VCC (+5V /w overcurrent monitor of both port 0 and 1)	
A2	DATAL0 (Differential data line paired with DATAH0)	
A3	DATAH0 (Differential data line paired with DATAL0)	
A4	GND	
B1	Fused VCC (+5V /w overcurrent monitor of both port 0 and 1)	
B2	DATAL1 (Differential data line paired with DATAH1)	
B3	DATAH1 (Differential data line paired with DATAL1)	
B4	GND	


Downloaded from www.Manualslib.com manuals search engine

5.3.6 ICMB Connectors

The external Intelligent Management Bus (ICMB) provides external access to IMB devices that are within the chassis. This makes it possible to externally access chassis management functions, alert logs, post-mortem data, etc. It also provides a mechanism for chassis power control.

As an option, the server can be configured with an ICMB adapter board to provide two SEMCONN 6-pin connectors to allow daisy chained cabling. Additional information about ICMB can be found in the *External Intelligent Management Bus Bridge External Program Specification*.


Table 40: ICMB Connector

Pin	Signal	ICMB Connector
1	Tx/Rx+	
2	Tx/Rx-	
3	GND	
4	No connection	
5	GND	
6	No connection	
7	No connection	
8	No connection	

5.3.7 100/10 Ethernet Connector (LAN 1)

The system supports one on-board 100/10 Ethernet connection.

Table 41: Ethernet Connector


Pin	Signal	100/10 Ethernet Connector
1	TX+	
2	TX-	
3	RX+	
4	Termination	
5	Termination	
6	RX-	
7	Termination	
8	Termination	

Downloaded from www.Manualslib.com manuals search engine

5.3.8 1000/100/10 Ethernet Connector (LAN 2)

The system supports one on board 1000/100/10 Ethernet connection.

Table 42: Ethernet Connector

Pin	Signal	100/100/10 Ethernet Connector
1	TR1+	
2	TR1-	
3	TR2+	
4	TR3+	
5	TR3-	
6	TR2-	
7	TR4+	
8	TR4-	

5.3.9 Internal SCA-2 HDD Connector

An SCA-2 connector is used on the primary side of the HDD backplane. The pin-out is the same as SCA-1. The connector pin assignment is for the current draft *Small Form Factor-8046 Rev. 1.1* document.

Table 43: SCA-2 Connector

80-pin connector contact and signal name			80-pin connector contact and signal name		
1	12 V Charge	(L)	(L)	12 V Ground	41
2	12 V	(S)	(L)	12 V Ground	42
3	12 V	(S)	(L)	12 V Ground	43
4	12 V	(S)	(S)	Mated 1	44
5	Reserved/ESI-1	(S)	(L)	-EFW	45
6	Reserved/ESI-2	(S)	(L)	DIFFSNS	46
7	-DB(11)	(S)	(S)	+DB(11)	47
8	-DB(10)	(S)	(S)	+DB(10)	48
9	-DB(9)	(S)	(S)	+DB(9)	49
10	-DB(8)	(S)	(S)	+DB(8)	50
11	-I/O	(S)	(S)	+I/O	51
12	-REQ	(S)	(S)	+REQ	52
13	-C/D	(S)	(S)	+C/D	53
14	-SEL	(S)	(S)	+SEL	54
15	-MSG	(S)	(S)	+MSG	55
16	-RST	(S)	(S)	+RST	56
17	-ACK	(S)	(S)	+ACK	57
18	-BSY	(S)	(S)	+BSY	58

Downloaded from www.Manualslib.com manuals search engine

80-pin connector contact and signal name			80-pin connector contact and signal name		
19	-ATN	(S)	(S)	+ATN	59
20	-DB(P)	(S)	(S)	+DB(P)	60
21	-DB(7)	(S)	(S)	+DB(7)	61
22	-DB(6)	(S)	(S)	+DB(6)	62
23	-DB(5)	(S)	(S)	+DB(5)	63
24	-DB(4)	(S)	(S)	+DB(4)	64
25	-DB(3)	(S)	(S)	+DB(3)	65
26	-DB(2)	(S)	(S)	+DB(2)	66
27	-DB(1)	(S)	(S)	+DB(1)	67
28	-DB(0)	(S)	(S)	+DB(0)	68
29	-DB(P1)	(S)	(S)	+DB(P1)	69
30	-DB(15)	(S)	(S)	+DB(15)	70
31	-DB(14)	(S)	(S)	+DB(14)	71
32	-DB(13)	(S)	(S)	+DB(13)	72
33	-DB(12)	(S)	(S)	+DB(12)	73
34	5V	(S)	(S)	Mated 2	74
35	5V	(S)	(L)	5 V Ground	75
36	5V Charge	(L)	(L)	5 V Ground	76
37	Spindle Sync	(L)	(L)	Active LED Out	77
38	MTRON	(L)	(L)	DLYD_START	78
39	SCSI ID (0)	(L)	(L)	SCSI ID (1)	79
40	SCSI ID (2)	(L)	(L)	SCSI ID (3)	80





Figure 18: SCA-2 Connector

Downloaded from www.Manualslib.com manuals search engine

5.3.10 External SCSI

As an option, the server system can support a shielded 68pin external VHDCI or SCSI3 connection. This connection is normally to Channel B of the onboard SCSI controller.

Table 44: SCSI Connector

Signal Name	Pin	SCSI Connector	Pin	Signal Name
Signal Return	1		35	-DB(12)
Signal Return	2		36	-DB(13)
Signal Return	3		37	-DB(14)
Signal Return	4		38	-DM(15)
Signal Return	5		39	-DB(P1)
Signal Return	6		40	-DB(0)
Signal Return	7		41	-DB(1)
Signal Return	8		42	-DB(2)
Signal Return	9		43	-DB(3)
Signal Return	10		44	-DB(4)
Signal Return	11		45	-DB(5)
Signal Return	12		46	-DB(6)
Signal Return	13		47	-DB(7)
Signal Return	14		48	-DB(P)
GND	15		49	GND
GND	16		50	GND
TERMPWR	17		51	TERMPWR
TERMPWR	18		52	TERMPWR
No connection	19		53	No connection
GND	20		54	GND
Signal Return	21		55	-ATN
GND	22		56	GND
Signal Return	23		57	-BSY
Signal Return	24		58	-ACK
Signal Return	25		59	-RST
Signal Return	26		60	-MSG
Signal Return	27		61	-SEL
Signal Return	28		62	-C/D
Signal Return	29		63	-REQ
Signal Return	30		64	-I/O
Signal Return	31		65	-DB(8)
Signal Return	32		66	-DB(9)
Signal Return	33		67	-DB(10)
Signal Return	34		68	-DB(11)

Downloaded from www.Manualslib.com manuals search engine

5.3.11 AC Power Input

Each power supply has an IEC320-C14 receptacle provided at the rear of the server. An appropriately sized power cord and AC main should be used. See Chapter 4 for system voltage, frequency and current draw specifications.




Figure 19: AC Power Input Connector

5.3.11.1 AC Power Cord Specification

The AC power cord supplied with the SPSH4 server system is the North American type. AC power cords must be rated for 100-240VAC voltage range, and have a low line current rating of at least 10A.

The wall outlet end of the AC power cord must be terminated in a grounding-type male plug designed for use in your region. The plug must have certification marks showing certification by an agency acceptable in your region.

The server end of the AC power cord must be an IEC 320, sheet C13, type female connector.

The AC power cord must be less than 4.5 meters (14.76 feet) long, and must be flexible (harmonized) cord or VDE-certified cordage to comply with server's safety certifications. The diameter of the AC power cord should be less the 0.25” to use the power supply module strain relief feature.

Downloaded from www.Manualslib.com manuals search engine

6. SCSI Bay Boardset

This chapter provides an overview of the LVD/SE SCSI boardset, describing the architecture of backplane boardset, and physical board layout diagrams.

The SCSI boardset consists of hot swap backplane and a SAF-TE board. The hot swap backplane supports the following features:

- SE SCSI and LVD SCSI modes
- Five 1 inch LVD/SE SCSI drives per board
- Single connector attachment (SCA-2) connectors to simplify insertion and removal of hard disk drives
- Insertion and removal of hard drives in any power or SCSI bus state (Hot Swap)
- FET power control for each hard drive
- FET short protection
- SCSI-2 SPI-2 (Ultra SCSI and Ultra2 SCSI) and SCSI-2 (Fast-10)
- SCSI-3 SPI-3 (Ultra-160 SCSI)
- SCSI-4 SPI-4 (Ultra-320 SCSI)
- Support for two backplanes on SCSI bus via “Y” cable
- Drive fault and drive activity LEDs for each disk drive

In addition, a SAF-TE addin card contributes the following features:

- Microcontroller to monitor enclosure services
- I^2C bus for management information
- Flash memory for upgrading firmware
- Thermal friendly mechanical form factor
- SAF-TE compliant
- Two-fan tachometer monitoring

6.1 Hot Swap Hard Drive Backplane

The backplane is a LVD/SE SCSI design that provides support for SCSI devices using Low Voltage Differential Signaling (Ultra-160 Ultra-320) as well as older SE SCSI devices (Ultra-160 and older). The backplane has a connector to accommodate a SAF-TE controller on an add-in card. The backplane supports five 1” hot swapping SCA-2 style drives when mounted in the docking drive carrier. By using a “Y” cable, two of these backplane assemblies may be connected for a total of ten SCSI drives off one SCSI channel.

Downloaded from www.Manualslib.com manuals search engine

6.1.1 Architectural Overview

The drive backplane is an integral part of the system chassis. It is designed to provide a cost effective ease of power-on (Hot Swap) drive replacement. It also provides easy RAID integration over a wide range of RAID controller products. It is designed to be vendor independent.

The feature that simplifies RAID integration is the addition of an on-board SCSI target whose command set allows vendor independent controller management and monitoring for associated drive functions such as: Drive insertion and removal, light indicators, and drive power control. Its use simplifies cable management and eliminates errors caused by the possibility of incorrect correlation of several cables.

The LVD/SE SCSI Backplane performs the tasks associated with hot-swappable SCSI drives, and enclosure (chassis) monitoring and management supported by the LVD/SE SCSI Backplane. They include, but are not limited to, the following:

- Monitoring the SCSI bus for enclosure services messages, and acting on them appropriately. Examples of such messages include:
  - Activate a drive fault indicator
  - Power down a drive, which has failed
  - Report fan tachometer status
- SAF-TE intelligent agent, which acts as proxy for “dumb” I^2C devices (that have no bus mastering capability) during intra-chassis communications.

6.2 Design Constraints and Assumptions

This section specifies certain assumptions and limitations taken into consideration during the design of the LVD/SE SCSI backplane.

6.2.1 SCSI Bus Considerations

The SCSI bus is based on the SPI-4 specification. It is designed to allow any SCSI device to communicate with any other SCSI device. To that end, SPI-4 requires that all SCSI devices be at certain distances apart, depending on the media capacitance measured in pF/m. The lower the media capacitance the greater the spacing needs to be because the loading from the device becomes more significant.

Historically, backplane designs have successfully violated this guideline because of careful simulation backed up with signal integrity validation. Those past designs were able to have straight-to-straight connections between three devices with some meandering between another three devices. The layout and board stackup was driven from LVD SCSI bus simulation, which yielded the following:

- SCA-2 to SCA-2 electrical distance of four inches
- Six-layer board with two internal SCSI layers with 90 Ohm impedance targeted
- Total backplane SCSI length max 30 inches

The electrical spacing of the SCA-2 connectors was a combination of the faster edge rate and faster transfer speed.

The following are key points to know:

Downloaded from www.Manualslib.com manuals search engine

- The LVD (Ultra2) length specification is 15 devices at 12 meters and 1-2 devices at 25 meters
- The SE (Ultra) length specification is 5-8 devices at 1.5 meters (59 inches) and 1-4 devices at 3 meter
- If used in SE Ultra mode, the backplane uses 30 of the 59 inches of the SCSI Bus length
- The backplane's SCSI interface counts as one device on the SCSI Bus regardless the presence of any SAF-TE compliant host controller.

6.3 Functional Description

This chapter defines the architecture of the LVD/SE SCSI Backplane, including descriptions of functional blocks and how they operate.

Figure 20 shows the functional blocks of the LVD/SE SCSI Backplane. The two boards are split such that the backplane has the SCSI connectors, drive fault/activity LEDs, and termination, and the SAF-TE addin card has the rest of the blocks. An overview of each block follows.




Figure 20: Functional Block Diagram

6.3.1 Wide SCSI Connector

SCSI input from Host SCSI Controller (baseboard or RAID card) in a press-fit connector.

6.3.2 SCA-2 Connectors

The LVD/SE SCSI backplane provides five SCA-2 connectors. These provide power and SCSI signals using a single connector. Each connector has control signals that enable the backplane to provide SCSI ID assignments as well as drive motor spin-up configuration. Each SCSI drive attaches to the backplane using one of these connectors.

Downloaded from www.Manualslib.com manuals search engine

6.3.3 SCSI Multi-ModeTermination

The multi-mode terminators provide SCSI-4 compliant termination for the backplane. These terminators provide termination in both SE modes and LVD mode.

6.3.4 SCSI Interface

The SCSI interface on the LVD/SE SCSI backplane provides the link between the SCSI bus and the microcontroller (containing the intelligence for the LVD/SE SCSI backplane). This interface allows the microcontroller to respond as a SCSI target to implement the SAF-TE protocol. This is implemented using a Symbios Logic* 53C80S SCSI interface chip (or equivalent).

6.3.5 Power Control

Power control on the LVD/SE SCSI backplane supports the following features. Without the population of the SAF-TE card, power to the drives is always on.

- Spin-down of a drive when failure is detected and reported (using enclosure services messages) via the SCSI bus. An application or RAID controller detects a drive-related problem that indicates a data risk. In response, it removes the drive from service and sends a spin-down SCSI command to the drive. This decreases the likelihood that the drive will be damaged during removal from the hot-swap drive bay. When a new drive is inserted, the power control waits a short amount of time for the drive to be fully seated before it applies power with a controlled power ramp.
- If the system power is on, the LVD/SE SCSI backplane immediately powers off a drive slot when it detects that a drive has been removed. This prevents possible damage to the drive when it is partially removed and re-inserted while full power is available, and disruption of the entire SCSI array from possible sags in supply voltage and resultant current spikes.

6.3.6 FET Short Protection

The FET short protection circuit is useful to protect both 12 volt and 5 volt power control FETs located on LVD/SE SCSI backplane.

Downloaded from www.Manualslib.com manuals search engine

6.3.7 Microcontroller

The microcontroller is an 80C652 microcontroller with a built-in I^2C interface. This provides the intelligence for the LVD/SE SCSI Backplane. The 80C652 microcontroller uses Flash for program code storage, and static RAM for program variables and buffers.

6.3.8 Device SCSI ID

Each device on a SCSI bus must have a unique SCSI ID. The 5 x 1.0" LVD/SE SCSI backplane device SCSI ID is dependant on whether it is configured as a primary or a secondary backplane. This configuration is defined by the logic of pin 1 on the I^2C connector (J2A1).

Table 45: SCSI ID Assignments

Device	SCSI ID as Primary Backplane I^2C connector (J2A1) pin1=1	SCSI ID as Primary Backplane I^2C connector (J2A1) pin1=0
Drive 1	0x0H	0x8H
Drive 2	0x1H	0x9H
Drive 3	0x2H	0xAH
Drive 4	0x3H	0xBH
Drive 5	0x4H	0xCH
SAF-TE Controller	0x6H	0x5H

6.3.9 Hard Drive Activity LED

Each SCSI drive turns on a green LED when it is accessed. The LEDs are 4-terminal dual-color (yellow and green) lights that are physically located on the backplane.

Table 46: Hard Drive Activity LED

Drive	HSBP LED Activated	LED Designator	LED Color
1	1	DS5A1	Green
2	2	DS5B1	Green
3	3	DS5C1	Green
4	4	DS5D1	Green
5	5	DS5E1	Green

Downloaded from www.Manualslib.com manuals search engine

6.3.10 Hard Drive Fault LED

The Hot-Swap Controller is responsible for turning the drive fault LEDs on or off according to the states specified via commands received via SAF-TE and the IMB. The drive fault LEDs are yellow and indicate the failure status for each drive. The LEDs are physically located on the LVD/SE SCSI Backplane. For further information on Slot Status to Fault Light State mapping refer to *SC5000 Hot-swap Controller Interface EPS.*

The LEDs are 4-terminal dual-color (yellow and green) physically located on the backplane.

Table 47: Hard Drive Fault LED

Drive	HSBP LED Activated	LED Designator	LED Color
1	1	DS5A1	Yellow
2	2	DS5B1	Yellow
3	3	DS5C1	Yellow
4	4	DS5D1	Yellow
5	5	DS5E1	Yellow

6.3.11 IMB (I^2C bus)

The I^2C bus is a system-wide server management bus. It provides a way for various system components to communicate independently of the standard system interfaces (e.g., PCI bus or processor/memory bus). The I^2C bus controller is integrated into the microcontroller.

6.3.12 Fan Support

The LVD/SE SCSI backplane supports up to two tach fans with a digital-output that can be used by the microcontroller to assess the fans' operating condition before total failure, which could result in hardware damage.

Microcontroller program code is responsible for monitoring the fan speed, which is directly controlled from backplane, and reporting the fan condition via the I^2C bus. The Hot-swap Controller is responsible for reporting fan speed. The speed of the fans is sensed by the Hot-swap Controller and compared against a 'low speed' threshold. The Hot-swap Controller issues a message on the IMB when the fan speed falls below this threshold. When a fan fails, it should be replaced; the backplane does not detect second fan failure.

6.3.13 Temperature

The DS1624 on the SAF-TE addin card provides a temperature sensor in the center of the SAF-TE addin card. This is accessed by a private I^2C bus.

6.3.14 Serial EEPROM

The DS1624 provides 256 bytes of non-volatile storage. This hold the serial number, part number, FRU inventory information, and miscellaneous application code used by firmware about the LVD/SE SCSI backplane. This is accessed by a private I^2C bus.

Downloaded from www.Manualslib.com manuals search engine

6.4 Board Functions

This section describes functioning parts as required by the *Management Bus Architecture Specification* and the *Enclosure Services SCSI Command Set*. In addition to these requirements, the board is capable of downloading code via IMB to update the FLASH executable code. The backplane functions begin at power-up. The microprocessor boots itself via code residing in the FLASH boot block.

6.4.1 Reset

A cold reset occurs when power is cycled or the SCSI bus can be reset by a SAF-TE command.

6.4.2 Microcontroller

The microcontroller is a Philips* P80C652FBB operating at 12 MHz. The 80C652 is a derivative of the 80C51 8-bit CMOS microcontroller. The 80C652 contains all of the features of the 80C51 (that is, the standard counter/timers T0 and T1, the standard serial I/O (UART), and four 8-bit I/O ports).

The organization of the data memory is similar to the 80C51 except that the 80C652 has an additional 128 bytes of RAM overlapped with the special function register space. This additional RAM is addressed using indirect addressing only and is available as stack space.

The 80C652 is pin-for-pin compatible and code compatible with the 80C51, except for additional Vss pins at the QFP package.

The features can be outlined as follows:

- Operating frequency from 1.2 MHz to 16 MHz
- 80C51-based architecture
- Four 8-bit I/O ports
- Two 16-bit timer/counters
- Full-duplex UART facilities
- I^2C Serial Interface
- Two power control modes; idle mode, power-down mode
- Operating temperature range: 0°C to +70°C

Downloaded from www.Manualslib.com manuals search engine

6.4.2.1 Special Function Registers

The 80C652 special function register space is the same as that on the 80C51 except that it contains four additional SFRs. The added registers are S1CON, S1STA, S1DAT, and S1ADR. In addition to these, the standard UART special function registers SCON and SBUF have been renamed S0CON and S0BUF for clarity.

Since the standard 80C51 on-chip functions are the same on the 80C652, the SFR locations, bit locations, and operation are unchanged. The only exception is in the interrupt enable and interrupt priority SFRs. These have been changed to include the interrupt from the I^2C serial port.

6.4.2.2 I^2C Serial Communication

The I^2C pins are alternate functions to port pins P1.6 and P1.7. Because of this, P1.6 and P1.7 on these parts do not have a pull-up structure as found of the 80C51. Therefore, P1.6 and P1.7 have open drain outputs on the 80C652.

6.4.2.3 I^2C Electrical Input/Output Specification

The I^2C bus allows communication between devices using different technologies that might also use different supply voltages.

For devices with fixed input levels, operating on a supply voltage of +5V $\pm$10%, the following levels have been defined:

- V_{Ilmax} = 1.5V (maximum input low voltage)
- V_{Ihmin} = 3V (minimum input High voltage)

Devices operating on a fixed supply voltage different from +5V (e.g. I^2L), must also have these input levels of 1.5V and 3V for V_{IL} and V_{IH} respectively.

For devices operating over a wide rage of supply voltages (e.g. CMOS), the following levels have been defined:

- $V_{Ilmax} = 0.3V_{DD}$ (maximum input Low voltage)
- $V_{Ihmin} = 0.7V_{DD}$ (minimum input High voltage)

For both groups of devices, the maximum output Low value has been defined:

- V_{Olmax} = 0.4V (max. output voltage Low) at 3ma sink current

The maximum low-level input current at V_{Olmax} of both the SDA pin and the SCL pin of an I^2C device is –10uA, including the leakage current of a possible output stage.

The maximum high-level input current at $0.9V_{DD}$ of both the SDA pin and SCL pin of an I^2C device is 10uA, including the leakage current of a possible output stage.The maximum capacitance of both the SDA pin and the SCL pin of an I^2C device is 10pf.

Downloaded from www.Manualslib.com manuals search engine

6.4.2.3.1 Noise Margin

- Noise margin minimum on the Low level is 0.1 V_{DD}.
- Noise margin minimum on the High level is 0.2 V_{DD}.

6.4.3 SCSI Controller

The SYM53C80S controller is an 8-bit controller. It is reset on power-up and when reset is asserted to the backplane.

SYM53C80S access slows down the bus, it is recommended to pulse SAF-TE infrequently. SAF_TE command processing is 2-10ms.

The features of the SCSI controller are as follows:

- Supports the ANSI X3.131-1994 standard
- Parity generation with optional checking
- No external clock required
- On-chip 48ma single-ended drivers and receivers
- Functions in both the target and initiator roles
- Direct control of all SCSI signals
- Asynchronous data transfers of up to 5.0 MB/second
- Variety of packaging options
- SCSI protocol efficiency is directly proportional to the speed of the microprocessor
- CMOS parts provide additional grounding and controlled fall times that reduce noise generated by SCSI bus switching
- SCAM Level 1 and 2 compatibility

6.4.4 Multi-Mode SCSI Termination

The SCSI-3 and SCSI-4 standards recommend the use of active termination at both ends of every cable segment in a SCSI system with single-ended drivers and receivers.

Two Unitrode* UCC5638 devices are used for active termination that detect SE or LVD mode and terminate appropriately.

6.5 Memory Map

This chapter describes the microcontroller memory map and individual regions of memory. 80C51 architecture allows up to 64KB of byte-addressable memory. No I/O map is provided, since 80C51 architecture makes no distinction between memory and I/O addresses (all I/O accesses are memory-mapped). However, four “I/O ports” available to the microcontroller are also defined in this chapter.

Downloaded from www.Manualslib.com manuals search engine

6.5.1 Memory Map

Figure 21 below shows the memory map viewed from the perspective of the microcontroller. Descriptions of each memory block are provided, showing their purpose and function as determined by microcontroller programming. These functions may also be controlled by system software using SCSI commands defined in the SAF-TE specification. Status and control regions act like an I/O port with many aliases.




Figure 21: Microcontroller Memory Map

6.5.1.1 Program Memory Region (0000h – 8FFFh)

Program memory is usually considered read-only. However, the Hot-swap SCSI Backplane is designed to allow writes to the program memory area, thereby supporting field-upgradeable code. The bottom 8 KB is the boot block, which can only be written to if the Flash Boot Block Write jumper is in the *write* position.

Downloaded from www.Manualslib.com manuals search engine

6.5.1.2 SCSI Memory Region (9000h – 9FFFh)

Buffer memory area for DMA transfers on the SCSI interface. Accesses to this region activate the appropriate DACK_L and Read/Write strobes to the 53C80S SCSI chip (which has been properly configured for DMA operations).

6.5.1.3 Drive Power Control/Status Region (A000h – AFFFh)

A read operation of any byte address within this region produces the current value of the Power Control byte. This value does not report the actual state of drive power (e.g., whether or not drive power is within specifications). Instead, this indicates whether the power for a particular drive has been switched on or off.

A write operation to any byte address within this region updates the current value of the Power Control byte, which causes selected drive slots to power on or off. The initial (default) value is 11011111b (all drives on). This allows normal server operation even if the firmware is corrupted or the microcontroller is not operational. The lower five bits function as power switches for each drive slot. The remaining three bits are read-only, and are defined below.

!WARNING!

If a drive is powered up immediately upon detection, it is likely to be damaged, as the drive will not be fully seated. It is recommended that firmware “debounce” the drive presence detect bits, and power up the drive no less than 250ms after the drive is detected as being present.

Table 48: Drive Power Status Byte Format

Bit(s)	Name	Description
7	Internal/External	Read only. Logic 1 indicates the backplane is installed in an “internal” chassis. Logic 0 indicates the backplane is installed in an “external” chassis (e.g. peripheral box).
6	Reserved	Reserved for future use.
5	SCSI ID	Read only. This bit determines the SCSI ID for the drive array.
4::0	DRVPWR[4::0]	Drive power control bits (read/write). Bit 0 corresponds to drive 0, bit 1 to drive 1, and so on. An active bit (1=active) indicates power is turned on for that drive; an inactive bit indicates power is turned off for that drive. Writing a 1 to a bit position turns on, or maintains power on, for the associated drive.

6.5.1.4 Fault Indicator Control Region (B000h – BFFFh)

A write operation to any byte address controls drive fault indicator LEDs. The value is initially 00h, which means all drive-fault LEDs are off. The lower five bits of the data byte function as on/off switches for each LED.

Downloaded from www.Manualslib.com manuals search engine

Table 49: Fault Indicator Control Byte Format

Bit(s)	Name	Description
7::5	Reserved	Reserved for future use.
4::0	FLTON[4::0]	Fault Indicator On. If 1, the fault LED is turned on, and if 0, turned off, on the drive associated with selected SCA connector. Bit 0 corresponds to backplane slot 0, etc. To avoid false indication of Drive fault on other drives, software should maintain a local copy of the last value written, modify the bit in this value that corresponds to the selected drive slot, before writing the new result.

6.5.1.5 Drive Presence Status Region (C000h – CFFFh)

A read operation of any byte address within this region produces a value that indicates the presence of the hard disks in the SCSI backplane.

Table 50: Drive Presence Status Byte Format

Bit(s)	Name	Description
7	Reserved	Reserved for future use.
6	Primary/Secondary or Low/High	Read only. Logic 1 indicates the backplane is the primary backplane in a chassis/system. Logic 0 indicates the backplane is the secondary backplane in a chassis/system. This corresponds to the SCSI ID jumper. • Low = Primary • High = Secondary
5	Force Update	Read only, active low. When active (low), the “Force firmware update” jumper has been moved to its active position. When inactive (high), the firmware on the backplane should operate as normal.
4::0	DRVPRSN[4::0]	Drive Present bits. A set bit indicates that a drive is physically present in the corresponding slot. Bit 0 corresponds to backplane slot 0, etc.

6.5.1.6 SCSI I/O Region (D000h – DFFFh)

Provides Read/Write access to the SCSI device as memory-mapped I/O. The 53C80S SCSI chip on the Hot-swap SCSI Backplane decodes three of the 12 address lines for this memory region. SCSI controller registers are addressed with an offset of D000h (i.e., I/O address 3Ah for the SCSI controller is physical address D03Ah).

6.5.1.7 Program and Data RAM Region (E000h – FFFFh)

This Read/Write memory region accesses 8 KB of RAM available for general usage. The hardware supports this memory region as both data memory and program memory. During normal operation, the microcontroller executes code from the program memory region (Flash). During the firmware upgrade process, the microcontroller executes code from the program and data RAM memory region.

Downloaded from www.Manualslib.com manuals search engine

6.5.2 I/O Ports

80C51 architecture provides four memory-mapped I/O ports:

- Port #0 (P0)
- Port #1 (P1)
- Port #2 (P2)
- Port #3 (P3)

6.5.2.1 P0

Since the firmware for the microcontroller is located in a Flash memory device (for ease of debugging and field upgradeability), and all memory and memory-mapped I/O are located outside the microcontroller, P0 is used as a time-multiplexed low-order address and data bus. It is not used for general I/O purposes.

Downloaded from www.Manualslib.com manuals search engine

6.5.2.2 P1

P1 has two dedicated-function signals, and six implementation specific control signals, as shown in Table 51.

Table 51: P1 Functions

Bit	Name	I/O	Fixed [1]	Function
7	SDA	I/O	Y	I^2C Serial Data signal for the intra-chassis I^2C bus.
6	SCL	I/O	Y	I^2C Serial Clock signal for the intra-chassis I^2C bus.
5	I2C_ADDR_CNTRL	I	N	I^2C address control: • 1=primary HSBP controller • 0=secondary HSBP controller Following the I^2C Address Allocation Specification the primary HSBP controller has an I^2C address of 0xC0 and the secondary controller has an I^2C address of 0xC2.
4	SCSI ctrlr reset	O	N	Reset SCSI controller. • If 0, places the 53C80S SCSI chip into reset • If 1, the SCSI interface chip comes out of reset and operates normally.
3	SCSI_DRQ	I	N	SCSI DMA Request. Connected to the DRQ signal of the 53C80S SCSI chip. Allows the microcontroller to use the DMA transfer capabilities of the SCSI interface chip, which results in higher performance.
2	Fan Power	O	N	Switches fan power on or off. • 0=on • 1=off
1	SDA_Local	I/O	N	Serial Data for private I^2C connection to temperature sensor
0	SCL_Local	O	N	Serial Clock for private I^2C connection to temperature sensor

1. "Fixed" indicates whether the function/pin is defined by the microcontroller pinout (fixed) or implementation-specific (not fixed)

6.5.2.3 P2

P2 is the high-order address and data bus for external device access. It is not used for general I/O purposes.

Downloaded from www.Manualslib.com manuals search engine

6.5.2.4 P3

P3 provides four dedicated function signals, and four implementation specific control signals, as shown in Table 52.

Table 52: P3 Functions

Bit	Name	I/O	Fixed 1	Function
7	RD_L	O	Y	Read strobe. Indication from the microcontroller that the current bus cycle is a read operation.
6	WR_L	O	Y	Write strobe. Indication from the microcontroller that the current bus cycle is a write operation.
5	Fan 2	I	N	Fan 2 tachometer input.
4	Fan 1	I	N	Fan 1 tachometer input.
3	INT1_L	I	Y	Interrupt 1. Connected to the SCSI bus reset signal RST_L.
2	INT0_L	I	Y	Interrupt 0. Connected to the 53C80S SCSI IRQ signal.
1	Reserved	-	N	Reserved for future use.
0	HSBP_SEL	I	N	SCSI backplane select: 0=5 x 1" LVD/SE SCSI Backplane; 1=3 x 1.6" LVD/SE SCSI Backplane.

1. "Fixed" indicates whether the function/pin is defined by the microcontroller pinout (fixed) or implementation-specific (not fixed).

6.6 Programming Information

This chapter describes briefly the programming and firmware information for the Hot-swap SCSI Backplane. The information in this section is an overview only. For detailed information, refer to *Hudson/Cabrillo-2 Hot-swap Controller Interface EPS*.

The firmware for the Hot-swap SCSI Backplane is stored in the Flash ROM. It is divided into two sections; the 8KB boot block area and the 24KB operational code area. The boot block area contains the basic IMB communication routines and the firmware transfer commands. The code in this area is permanently stored and can only be updated if the Flash Boot Block Update jumper is in the proper position. The operational code area contains the run-time code, including the SCSI and SAF-TE routines, monitoring routines, and IMB routines. All code in this area can be updated using the firmware transfer commands.

Downloaded from www.Manualslib.com manuals search engine

6.6.1 Firmware Support Requirements

See the *Hudson/Cabrillo-2 Hot-swap Controller Interface EPS*.

6.6.1.1 Software Upgrade Process

Firmware update is accomplished by entering Firmware Transfer Mode, either through an IMB command or by placing the Firmware Update Jumper in the Force Update position. The jumper position can be changed only when the system is powered off. Firmware transfers are done only through the IMB.

If an IMB command was used to enter Firmware Transfer Mode, the corresponding exit command is used to return to normal operation. If the jumper was used, the system must be powered down and the jumper restored to the Normal Operation position to return to Operational Mode.

6.7 External Interface Specifications

This chapter specifies electrical characteristics of the connector pins.

6.7.1 Connector Specifications

Table 53 shows the quantity, manufacturers, and Intel part numbers for connectors on the LVD/SE SCSI Backplane. Refer to the manufacturers' documentation for more information on connector mechanical specifications.

Table 53: Connector Specifications

Item	Qty.	Manufacturer(s) and Part #	Description
1	2	TYCO* (794697-1) Intel P/N (107774-005)	4-pin (1x4) power connector
2	2	Molex* (22-05-3031) Intel P/N (109786-004)	1x3 RA fan header
3	1	Molex (22057045) Intel P/N (739197-001)	4-pin (1x4) I^2C connector
4	5	FCI-BERG* (72436-003) Intel P/N (626530-382)	80-pin SCA-2 connector
5	1	Foxconn* (EH06099) Intel P/N (201082-565	PCI connector
6	1	TYCO (788644-7) Intel p/n (A03228-001)	68-pin SCSI pressfit input connector

Downloaded from www.Manualslib.com manuals search engine

6.7.2 SCSI Input Connector 68P

The SCSI input connector is a non-shielded device connector.




Figure 22: SCSI Input connector 68P Non-Shielded


Table 54: SCSI Input connector (J1D1)

Signal Name	Connector Contact Number	SCSI Bus Conductor Number	SCSI Bus Conductor Number	Connector Contact Number	Signal Name
+DB(12)	1	1	2	35	-DB(12)
+DB(13)	2	3	4	36	-DB(13)
+DB(14)	3	5	6	37	-DB(14)
+DB(15)	4	7	8	38	-DB(15)
+DB(P1)	5	9	10	39	-DB(P1)
+DB(0)	6	11	12	40	-DB(0)
+DB(1)	7	13	14	41	-DB(1)
+DB(2)	8	15	16	42	-DB(2)
+DB(3)	9	17	18	43	-DB(3)
+DB(4)	10	19	20	44	-DB(4)
+DB(5)	11	21	22	45	-DB(5)
+DB(6)	12	23	24	46	-DB(6)
+DB(7)	13	25	26	47	-DB(7)
+DB(P)	14	27	28	48	-DB(P)
GND	15	29	30	49	GND
GND	16	31	32	50	GND
RESERVED	17	33	34	51	RESERVED
RESERVED	18	35	36	52	RESERVED
RESERVED	19	37	38	53	RESERVED
GND	20	39	40	54	GND
+ATN	21	41	42	55	-ATN
GND	22	43	44	56	GND
+BSY	23	45	46	57	-BSY
+ACK	24	47	48	58	-ACK
+RST	25	49	50	59	-RST

Downloaded from www.Manualslib.com manuals search engine

Signal Name	Connector Contact Number	SCSI Bus Conductor Number	SCSI Bus Conductor Number	Connector Contact Number	Signal Name
+MSG	26	51	52	60	-MSG
+SEL	27	53	54	61	-SEL
+C/D	28	55	56	62	-C/D
+REQ	29	57	58	63	-REQ
+I/O	30	59	60	64	-I/O
+DB(8)	31	61	62	65	-DB(8)
+DB(9)	32	63	64	66	-DB(9)
+DB(10)	33	65	66	67	-DB(10)
+DB(11)	34	67	68	68	-DB(11)

SCSI SCA-2 Drive Connector



Note: In this board SCA-2 PressFit connector is used on the secondary side of the board.

Figure 23: SCA-2 Connector 80P

Table 55: SCA-2 Connectors (J3E1, J3D1, J3C1, J3B1, J3A1)

Pin	80pin connector contact and signal name		Pin	80pin connector contact and signal name	
1	12V PreCharge	(L)	41	12V Ground	(L)
2	12V	(S)	42	12V Ground	(L)
3	12V	(S)	43	12V Ground	(L)
4	12V	(S)	44	Mated 1	(S)
5	3.3V	(S)	45	3.3V PreCharge	(L)
6	3.3V	(S)	46	DIFFSNS	(L)
7	-DB(11)	(S)	47	+DB(11)	(S)
8	-DB(10)	(S)	48	+DB(10)	(S)
9	-DB(9)	(S)	49	+DB(9)	(S)
10	-DB(8)	(S)	50	+DB(8)	(S)
11	-I/O	(S)	51	+I/O	(S)
12	-REQ	(S)	52	+REQ	(S)
13	-C/D	(S)	53	+C/D	(S)
14	-SEL	(S)	54	+SEL	(S)
15	-MSG	(S)	55	+MSG	(S)
16	-RST	(S)	56	+RST	(S)

Downloaded from www.Manualslib.com manuals search engine

17	-ACK	(S)	57	+ACK	(S)
18	-BSY	(S)	58	+BSY	(S)
19	-ATN	(S)	59	+ATN	(S)
20	-DB(P)	(S)	60	+DB(P)	(S)
21	-DB(7)	(S)	61	+DB(7)	(S)
22	-DB(6)	(S)	62	+DB(6)	(S)
23	-DB(5)	(S)	63	+DB(5)	(S)
24	-DB(4)	(S)	64	+DB(4)	(S)
25	-DB(3)	(S)	65	+DB(3)	(S)
26	-DB(2)	(S)	66	+DB(2)	(S)
27	-DB(1)	(S)	67	+DB(1)	(S)
28	-DB(0)	(S)	68	+DB(0)	(S)
29	-DB(P1)	(S)	69	+DB(P1)	(S)
30	-DB(15)	(S)	70	+DB(15)	(S)
31	-DB(14)	(S)	71	+DB(14)	(S)
32	-DB(13)	(S)	72	+DB(13)	(S)
33	-DB(12)	(S)	73	+DB(12)	(S)
34	5V	(S)	74	Mated 2	(S)
35	5V	(S)	75	5V Ground	(L)
36	5V PreCharge	(L)	76	5V Ground	(L)
37	Spindle Sync	(L)	77	Active LED Out	(L)
38	RMT_START	(L)	78	DLYD_START	(L)
39	SCSI ID (0)	(L)	79	SCSI ID (1)	(L)
40	SCSI ID (2)	(L)	80	SCSI ID (3)	(L)

6.7.3 I^2C Connector

Table 56: I^2C Connector (J2A1)

Pin	Signal
1	I2C_ADDR_CNTRL
2	IMB_CLK
3	GND
4	IMB_SDA

Downloaded from www.Manualslib.com manuals search engine

6.7.4 Power Connector

Table 57: Power Connector (J4A1, J3A2)

Pin	Signal
1	12V
2	GND
3	GND
4	+5V

6.7.5 Fan 3-pin Connector

There are two 3-pin fan connectors on the backplane. Table 58 shows the pin-out of each connector. Fan power is defaulted to a voltage close to +12V and can be controlled by the SAF-TE card to be turned off.

Table 58: Fan Connector

Pin	Signal (J2A2)	Signal (J2A3)
1	GND	GND
2	FAN1 (tach)	FAN2 (tach)
3	Fan power	Fan power

6.7.6 SAF-TE PCI Connector Interface

The PCI connector interfaces the LVD bus to the AIC3860 on the SAF-TE card.

Downloaded from www.Manualslib.com manuals search engine

Table 59: PCI connector (J5C1)

Pin	Signal	Pin	Signal
A1	FAULT_L:4	B1	GND
A2	LVD_SCSI:1	B2	LVD_SCSI:0
A3	LVD_SCSI:28	B3	LVD_SCSI:27
A4	LVD_SCSI:3	B4	LVD_SCSI:2
A5	LVD_SCSI:30	B5	LVD_SCSI:29
A6	LVD_SCSI:5	B6	LVD_SCSI:4
A7	LVD_SCSI:32	B7	LVD_SCSI:31
A8	LVD_SCSI:7	B8	LVD_SCSI:6
A9	LVD_SCSI:34	B9	LVD_SCSI:33
A10	LVD_SCSI:9	B10	LVD_SCSI:8
A11	LVD_SCSI:36	B11	LVD_SCSI:35
A12	LVD_SCSI:11	B12	LVD_SCSI:10
A13	LVD_SCSI:38	B13	LVD_SCSI:37
A14	LVD_SCSI:13	B14	LVD_SCSI:12
A15	LVD_SCSI:40	B15	LVD_SCSI:39
A16	LVD_SCSI:15	B16	LVD_SCSI:14
A17	LVD_SCSI:42	B17	LVD_SCSI:41
A18	LVD_SCSI:17	B18	LVD_SCSI:16
A19	LVD_SCSI:44	B19	LVD_SCSI:43
A20	LVD_SCSI:19	B20	LVD_SCSI:18
A21	LVD_SCSI:46	B21	LVD_SCSI:45
A22	LVD_SCSI:21	B22	LVD_SCSI:20
A23	LVD_SCSI:48	B23	LVD_SCSI:47
A24	LVD_SCSI:23	B24	LVD_SCSI:22
A25	LVD_SCSI:50	B25	LVD_SCSI:49
A26	LVD_SCSI:25	B26	LVD_SCSI:24
A27	LVD_SCSI:52	B27	LVD_SCSI:51
A28	LVD_SCSI:53	B28	LVD_SCSI:26
A29	GND	B29	GND
A30	DRVPRSN:0	B30	TP_DRVACT:0
A31	DRVPRSN:1	B31	TP_DRVACT:1
A32	DRVPRSN:2	B32	TP_DRVACT:2
A33	DRVPRSN:3	B33	TP_DRVACT:3
A34	DRVPRSN:4	B34	TP_DRVACT:4
A35	GND	B35	GND
A36	DIFFSENSE	B36	PWRON:0
A37	FAN_CNTRL	B37	PWRON:1
A38	FAN1_TACH	B38	PWRON:2
A39	FAN2_TACH	B39	PWRON:3
A40	GND	B40	PWRON:4
A41	IMB_SDA	B41	GND
A42	IMB_CLK	B42	VCC

Downloaded from www.Manualslib.com manuals search engine

Pin	Signal	Pin	Signal
A43	I2C_ADDR_CNTRL	B43	VCC
A44	GND	B44	GND
A45	GND	B45	GND
A46	GND	B46	GND
A47	GND	B47	+12V
A48	GND	B48	+12V
A49	GND	B49	GND
A50	N/C	B50	N/C
A51	N/C	B51	N/C
A52	GND	B52	GND
A53	GND	B53	GND
A54	GND	B54	GND
A55	GND	B55	GND
A56	GND	B56	GND
A57	GND	B57	GND
A58	GND	B58	GND
A59	FAULT_L:3	B59	GND
A60	FAULT_L:2	B60	GND
A61	FAULT_L:1	B61	GND
A62	FAULT_L:0	B62	GND

Downloaded from www.Manualslib.com manuals search engine

6.8 Cables

6.8.1 Signal Cables

One Wide SCSI cable connects the embedded PCI SCSI controller card on the baseboard and one cable connects I^2C from either the front panel or the baseboard.

6.8.2 Power Cables

Two power cables, from peripheral devices to the disk backplane and one fan cable connects the fans to the disk backplane.

6.9 Mechanical Specifications




Figure 24: Hotswap Backplane Mechanical Drawing

Downloaded from www.Manualslib.com manuals search engine




Figure 25: SAF-TE Addin Card Mechanical Drawing

Downloaded from www.Manualslib.com manuals search engine

7. System Boards

This chapter describes the design and features of the SPSH4 system boards.

7.1 Power Distribution Board

The SPSH4 server system power supplys plug into a power distribution board (PDB). The PDB provides power connectivity and server management features to the server system. The PDB is located in the base of the chassis. Right-angle connectors on the PDB allow the blind-mating of up to three power supply connectors. Two pop rivets and four 6-32 screws are used to secure this board to the chassis mounting bracket.

The following power supply functions are monitored and reported to the I^2C bus by an ADM1026 IC on the PDB board:

- Power supply fan failure monitoring
- ACOK monitoring indicate when AC to each power supply is within regulation to insure proper system turn on even during a brownout recovery situation
- Power supply presence monitoring
- Power supply predictive failure monitoring
- Power supply failure monitoring
- SCSI bay fan failure monitoring
- Field Replaceable Unit (FRU) information access for the PDB

The ADM1026 has an I^2C slave address of 0x5A/5Bh.

The PDB board has an ISPLSI2032 power PLD, which is used manage the power-on and power-good functionality. Power supply predictive fail, fail, present, and ACOK are monitored by the power PLD. Power supply fan speed is controlled via signal outputs from the power PLD, the speed control is either at high speed or at normal speed depending upon the state of the server system.

The PDB also determines the I^2C slave addresses for the three power supply modules as follows: PS1 = 0xA0/A1h, PS2 = 0xA2/A3h, PS3 = 0xA6/A7h.

Downloaded from www.Manualslib.com manuals search engine

7.1.1 Board Layout




Figure 26: Fan Board Layout

7.1.2 Connector Pinouts

Table 60: Signal Pins and Power Blades (PS1, PS2, PS3)

Signal Pins										
	1	2	3	4	5	6				
D	-12V	RS GND	Reserved	Reserved	PWR OK	+12V LSS				
C	Reserved	RS +12V	PRDCT FAIL	FAIL	I2C SCL	A1				
B	+5V Standby	Reserved	RS +5V	RS +3.3V	I2C SDA	A2				
A	PSKILL	PSON*	+5V LSS	FANC	PRESENT*	+3.3V LSS				
Power Blades										
P1	**P2**	**P3**	**P4**	**P5**	**P6**	**P7**	**P8**	**P9**	P10	P11
+3.3V	+3.3V	+5V	+5V	GND	GND	GND	GND	GND	+12V	Reserved

Notes:

- Signals that can be defined as low true use the following convention: *signal** = low true.
- Intel does not support interchanging power supplies between SPSH4 and SPKA4 systems.

Downloaded from www.Manualslib.com manuals search engine




Figure 27: Power supply Mating Connector Pin Locations

Note: The pin on the power supply connector that mates with position A1 will be shorter than all others for PSKILL implementation.

Table 61: Main Power #1 Connector (P5)

Pin	Signal	Pin	Signal
1	+3.3V	13	+3.3V
2	+3.3V	14	+3.3V
3	+3.3V	15	+3.3V
4	GND	16	GND
5	GND	17	GND
6	GND	18	GND
7	GND	19	GND
8	GND	20	GND
9	+12V	21	+12V
10	+12V	22	+12V
11	+12V	23	+12V
12	+12V	24	+12V

Table 62: Main Power #2 Connector (P4)

Pin	Signal	Pin	Signal
1	+12V	11	+5VSB
2	GND	12	GND
3	GND	13	GND
4	GND	14	GND
5	GND	15	GND
6	+5 V	16	+5 V
7	+5 V	17	+5 V
8	+5 V	18	+5 V
9	+5 V	19	+5 V
10	+5 V	20	+5 V

Downloaded from www.Manualslib.com manuals search engine

Table 63: Main Power Control Connector (P6)

Pin	Signal	Pin	Signal
1	GND	2	+5V remote sense
3	+3.3V remote sense	4	GND
5	I^2C clock	6	I^2C data
7	GND	8	Power supply good
9	Power supply ON	10	GND
11	-12V	12	No Pin
13	+12V remote sense	14	Remote sense return

Table 64: Fan/Peripheral Power Connector (P1)

Pin	Signal	Pin	Signal
1	+12V	10	+12V
2	No connection	11	No connection
3	GND	12	GND
4	+12V	13	+5V
5	GND	14	GND
6	+12V	15	+5V
7	GND	16	GND
8	+12V	17	+5V
9	GND	18	GND

Table 65: Primary SCSI Bay Power Connector (P2)

Pin	Signal	Pin	Signal
1	+12V	5	+5V
2	GND	6	GND
3	+12V	7	+5V
4	GND	8	GND

Table 66: Seconday SCSI Bay Power Connector (P3)

Pin	Signal	Pin	Signal
1	+12V	5	+5V
2	GND	6	GND
3	+12V	7	+5V
4	GND	8	GND

Downloaded from www.Manualslib.com manuals search engine

7.2 Front Panel Board

The front panel board has five momentary switches and six LEDs visible through the chassis front bezel. The five switches control power on/off, sleep mode, system reset, chassis ID, and NMI. These switches are behind the front door of the bezel. The NMI switch is accessible via a small hole in the front of the chassis and requires a small instrument to push it.

The six front panel LEDs are:

- Power-on LED: Sold green indicates system power in a steady-on state and blinking green indicates Advanced Configuration and Power Interface (ACPI) sleep mode
- LAN 1 activity LED: Green during network activity
- LAN 2 activity LED: Green during network activity
- HDD activity LED: Green indicates system hard drive activity and amber indicates hard drive fault
- Chassis ID LED: Blue LED provides system identification to aid in servicing
- System status: Green indicates normal system status and amber indicates fault for power supply, hard drive, or cooling subsystem.

The front panel also contains seven connectors:

- A 34-pin connector provides control and status information to/from the baseboard.
- Two internal 10-pin connectors provide data and power for the USB and serial port B RJ45 ports
- Two external connectors provide data and power for the external USB and RJ-45 Serial B ports
- Two connectors are for chassis intrusion switches.

The front panel board mounts to sheetmetal at the front of the system and this is secured to the chassis with one 6-32 screw.

In addition, the front panel board has a 24C02LM8 serial EEPROM for Field Replaceable Unit information access. The 24C02LM8 has an I^2C slave address of 0xA0/A1h.The front panel board has a DS1621S digital thermostat for measuring ambient air temperature into the server system. The DS1621S has an I^2C slave address of 0x9A/9Bh.

Downloaded from www.Manualslib.com manuals search engine

7.2.1 Board Layout




Figure 28: Fan Board Layout

Downloaded from www.Manualslib.com manuals search engine

7.2.2 Connector Pinouts

Table 67: Front Panel Signal Connector (P5)

Pin	Signal	Pin	Signal
1	PWR_LED_PWR	2	+5VSB
3	No pin	4	FAN_FAIL_PWR
5	PWR_LED-0	6	PWR_FAULT-0
7	HDD_ACT_PWR	8	No connection
9	HDD_ACT-0	10	PWR_FAULT-0
11	PWR_SW-0	12	NIC1_ACT_PWR
13	GND	14	NIC1_ACT-0
15	RESET_SW-0	16	I2C_SDA
17	GND	18	I2C_SCL
19	SLEEP_SW-0	20	CI
21	GND	22	NIC2_ACT_PWR
23	NMI_SW-0	24	NIC2_ACT-0
25	No pin	26	No pin
27	ID_LED_PWR	28	No connection
29	ID_LED-0	30	STATUS_LED-0
31	ID_SW-0	32	No connection
33	GND	34	HDD_FAULT-0

Table 68: USB Port 3 Input Connector (P7)

Pin	Signal	Pin	Signal
1	No connection	2	USBP3_VCC
3	No connection	4	USB_P3_N
5	No connection	6	USB_P3_P
7	No connection	8	USBP3_GND
9	No Pin	10	GND

Table 69: USB Port 3 (P2)

Pin	Signal
1	USBP3_VCC
2	USB_P3_N
3	USB_P3_P
4	USBP3_GND

Downloaded from www.Manualslib.com manuals search engine

Table 70: Serial Port B Input Connector (P6)

Pin	Signal	Pin	Signal
1	No connection	2	SIODSR+00
3	SIORXD+00	4	SIORTS+00
5	SIOTXD+00	6	SIOCTS+00
7	SIODTR+00	8	SIORI+00
9	GND	10	No Pin

Table 71: RJ45 Serial Port B (P1)

Pin	Signal
1	SIORTS+00
2	SIODTR+00
3	SIOTXD+00
4	GND
5	SIORI+00
6	SIORXD+00
7	SIODSR+00
8	SIOCTS+00

Table 72: Chassis Intrusion Connector 1 (P4)

Pin	Signal
1	CI
2	Connect to pin 1 of CI connector 2

Table 73: Chassis Intrusion Connector 2 (P3)

Pin	Signal
1	Connect to pin 2 of CI connector 1
2	GND

Downloaded from www.Manualslib.com manuals search engine

7.3 Fan Distribution Board

The SPSH4 fan distribution board (FDB) provides power, speed control, tachometer monitoring, and presence detect for the six system fans. The fan board snaps into the chassis fan baffle part and does not require any screws to secure it.

The fan board is populated with two 80mm fans and two dual 120mm fan banks (two 120mm fans grouped together to form the fan bank).

Amber LEDs on the fan board indicate a fan bank fault condition. These LEDs can be viewed when the chassis front top cover is removed. Fan bank fault condition is generated by server management from either a missing fan presence signal or from too slow of a fan tachometer reading.

The speed of the system fans is controlled by pulse width modulation (PWM) of power. PWM control of fan speed is implemented by toggling fan power between +12V and +5V power rails. This is done via a server management control signal input to a power FET. In the event of a fault or over temperature condition, only +12V power is applied to all fans thus providing maximum fan speed and cooling capability. In addition, fan power is fused to improved system availability in the event of a fan fault.

7.3.1 Board Layout




Figure 29: Fan Board Layout

7.3.2 Connector Pinouts

Table 74: Power Connector (P5)

Pin	Signal	Pin	Signal
1	+12V	4	+12V
2	No connection	5	No connection
3	GND	6	GND

Downloaded from www.Manualslib.com manuals search engine

Table 75: Front 120mm Fan Bank Connector (P1)

Pin	Signal	Pin	Signal
1	No connection	6	No connection
2	FPRESMF-0	7	GND
3	FANMFPOW+0	8	MFSENSE+0
4	GND	9	FANRFPOW+0
5	RFSENSE+0	10	FPRESRF-0

Table 76: Front 80mm Fan Connector (P2)

Pin	Signal	Pin	Signal
1	LFSENSE+0	3	FANLFPOW+0
2	GND	4	FPRESLF-0

Table 77: Rear 120mm Fan Bank Connector (P3)

Pin	Signal	Pin	Signal
1	No connection	6	No connection
2	RPRESMF-0	7	GND
3	FANMFPOW+0	8	MRSENSE+0
4	GND	9	FANRFPOW+0
5	RRSENSE+0	10	RPRESRR-0

Table 78: Rear 80mm Fan Connector (P4)

Pin	Signal	Pin	Signal
1	LRSENSE+0	3	FANLFPOW+0
2	GND	4	RPRESLR-0

Downloaded from www.Manualslib.com manuals search engine

Table 79: Fan Signal Connector (P6)

Pin	Signal	Pin	Signal
1	RPRESLR-1	2	RPRESMR-1
3	REARPCILED+0	4	RPRESRR-1
5	LRSPEED+0	6	FPRESLF-1
7	LRSENSE+1	8	FPRESMF-1
9	GND	10	FPRESRF-1
11	RFLED+0	12	+5V
13	No connection	14	No connection
15	RFSENSE+1	16	No connection
17	GND	18	RRLED+0
19	MFLED+0	20	+5V
21	No connection	22	RRSPEED+0
23	MFSENSE+1	24	RRSENSE+1
25	GND	26	MRLED+0
27	FRNTPCILED+0	28	+5V
29	No connection	30	MRSPEED+0
31	LFSENSE+1	32	MRSENSE+1
33	GND	34	+5V

7.4 HPIB Board

The SPSH4 hot plug indicator board (HPIB) provides power on and status LEDs for hot plug PCI-X adapters. Power can be cycled to four hot plug PCI-X adapters via software or via individual magnetic switches actuated by a mechanical latches retaining the PCI-X adapters.

The mechanical latch releases the PCI-X adapter filler panel and can be accessed from inside the system. Two pop rivets secure this board.

LEDs can be viewed from both inside and outside the system and indicate the functional state of the hot plug PCI-X adapter slots.

- A green LED indicates power to the hot plug slot is on.
- An yellow LED indicates there is a fault on the hot plug slot.
- A blinking green LED indicates power is transitioning on the hot plug slot.

Slots 5 through 8 are hot-plug PCI-X and slots 1 through 4 are non-hot plug PCI. See Figure 30 for slot numbering sequence.

Downloaded from www.Manualslib.com manuals search engine

7.4.1 Board Layout




Figure 30: HPIB Board Layout

7.4.2 Connector Pinouts

Table 80: HPIB Signal Connector (P1)

Pin	Signal	Description	Pin	Signal	Description
1	+3.3Vstandby	Switch power	2	+5V	LED power
3	GND	GND	4	GND	GND
5	No connection	–	6	No connection	–
7	No connection	–	8	No connection	–
9	SLT31SW-00	Switch – slot 5 : C1	10	SLT32SW-00	Switch – slot 6 : C2
11	SLT41SW-00	Switch – slot 7 : D1	12	SLT42SW-00	Switch – slot 8 : D2
13	No connection	–	14	No connection	–
15	No connection	–	16	No connection	–
17	No connection	–	18	No connection	–
19	No connection	–	20	No connection	–
21	ATTEN310-10	Yellow LED – slot 5 : C1	22	ATTEN311-10	Green LED – slot 5 : C1
23	ATTEN320-10	Yellow LED – slot 6 : C2	24	ATTEN321-10	Green LED – slot 6 : C2
25	ATTEN410-10	Yellow LED – slot 7 : D1	26	ATTEN411-10	Green LED – slot 7 : D1
27	ATTEN420-10	Yellow LED – slot 8 : D2	28	ATTEN421-10	Green LED – slot 8 : D2

Downloaded from www.Manualslib.com manuals search engine

7.5 ICMB Board

The SPSH4 ICMB board complies with requirements for an SSI midrange server. This board passes ICMB data signals from the SSH4 baseboard to two keyed RJ45 ports. The ICMB board mounts to a sheetmetal bracket located at the rear panel of the system with two 4-40 screws and this bracket is then secured to the chassis with one 6-32 screw.

7.5.1 Board Layout




Figure 31: ICMB Board Layout

7.5.2 Connector Pinouts

Table 81: Keyed RJ45 ICMB Port Connectors (P1 & P2)

Pin	Signal
1	Tx/Rx+
2	Tx/Rx-
3	GND
4	No connection
5	GND
6	No connection
7	No connection
8	No connection

Downloaded from www.Manualslib.com manuals search engine

Table 82: ICMB Signal Connector to Baseboard (P3)

Pin	Signal
1	XP05S
2	ICMB_TX
3	ICMB_TX_ENB
4	ICMB_RX
5	GND

Downloaded from www.Manualslib.com manuals search engine

8. Hardware Configuration

8.1 System Configuration

SPSH4 server system is available in a pedestal or rack mount versions. These configurations are described in Table 83.

Table 83: System Configuration

Feature	Black Pedestal	Beige Pedestal	Black Rack
Chassis	1	1	1
Pedestal front bezel (black) with feet, chassis covers (black)	1	0	0
Pedestal front bezel (beige) with feet, chassis covers (beige)	0	1	0
Rack front bezel (black) with handles, chassis covers (unpainted)	0	0	1
SSH4 baseboard	1	1	1
SSH4 processor board	1	1	1
SSH4 memory board	1	1	1
Front panel board	1	1	1
Hot plug indicator board	1	1	1
Fan distribution board	1	1	1
Power distribution board	1	1	1
600W power supplys	2	2	2
1” Floppy drive (black)	1	1	1
5¼” CD-ROM drive (black)	1	1	1
5 x 1” HDD bay (black) + cooling fan [1]	1	1	1
System fans [1]	6	6	6
Resource kit (2 AC power cords, resource CD, ISM CD, 5¼” rails & screws)	1	1	1
Welcome Mat	1	1	1
Rack slide rail kit	0	0	0
Processors	0	0	0
DDR DRAM modules	0	0	0
SCSI hard disk drives	0	0	0

Notes:

1. There are three types of fan modules:
   - Fans for cooling the PCI section consist of a single 80mm fan
   - Fan banks for cooling the processor section consist of a bank of two 120mm fans
   - Fans for cooling the SCSI hard drives consist of a single 92mm fan

Downloaded from www.Manualslib.com manuals search engine

8.2 Spares / Accessories

SPSH4 server system comes with several spares and accessories as outlined in Table 84.

Table 84: Spare / Accessory List

Spare/Accessory	Description	Min Order
Baseboard	SSH4 baseboard ("Shasta") using ServerWorks ServerSet IV Grand Champion HE Chipset.	1
Processor board	SSH4 processor board	1
Memory board	SSH4 DDR DRAM memory module	1
Power supply	600W SPSH4 power supply including US power cord	1
1” x 5 hard drive bay	SCSI hard drive bay supporting up to five 1” hard drives, cables, cooling fan, and installation instructions	1
1” hard drive carrier	1” black hard drive carrier with mounting screws	10
ICMB kit	ICMB board, cable, mounting hardware and assembly instructions	1
Fan kit	120mm dual fan bank, 80mm fan, 92mm fan	1
System board kit	Fan board, front panel board, HPIB, and PDB	1
Integrator parts kit	Includes replacement screws, rivets, gaskets, processor installation parts, and other plastic parts	1
Rack kit	Rack slide rails, nut clips, mounting hardware, and assembly instructions	1
DLT rail kit	SPSH4 DLT Rail Kit supporting 5 DLT drives (10-pack - 1 DLT drive requires 2 rails)	10
Cable kit	All SPSH4 cables (except for PCI and external SCSI cables)	1
PCI SCSI cable	Cable from RAID PCI adapter card to HDD bay	5
External SCSI cable	Cable from PCI adapter card to external port	5
5.25” bay SCSI cable	Cable from baseboard to 5.25” peripheral devices (includes LVD/SE terminator)	5
Retention module kit	Set of four processor retention modules, screws, and assembly instructions	1

Downloaded from www.Manualslib.com manuals search engine

9. Product Regulatory Compliance Specifications

The SPSH4 server system meets the following safety and EMC specifications.

9.1 Product Safety Compliance

Table 85: Product Safety Compliance

Country	Standard
USA/Canada	UL60 950 – 3rd Edition
European Union	EN60 950 Low Voltage Directive, 73/23/EEC (CE Mark)
Nordic Countries	EMKO-TSE (74-SEC) 207/94
Russia	GOST R 50377-92
Argentina	IRAM – Resolution No. 92/98
International	IEC60 950 3rd Edition

9.2 Product EMC Compliance

Table 86: Product EMC Compliance

Country	Standard
USA	FCC 47 CFR Parts 2 and 15, Class A Limit, Radiated & Conducted Emissions
Canada	ICES-003, Class A Limit, Radiated & Conducted Emissions
Europe	EMC Directive, 89/336/EEC (CE Mark) EN55022, Class A Limit, Radiated & Conducted Emissions EN55024 (Immunity) EN61000-3-2 / EN610003-3, Harmonic Currents / Voltage Flicker
Russia	GOST R 29216-91, Class A Limit, Radiated & Conducted Emissions GOST R 50628-95 (Immunity)
Australia/New Zealand	AS/NZS 3548, Class A Limit, Radiated & Conducted Emissions
Taiwan	BSMI, CNS13438, Class A Limit, Radiated & Conducted Emissions
Korea	RRL, MIC Notices No 1997-41 & 1997-42, Class A Limit, Radiated & Conducted Emissions
Japan	VCCI, (via CISPR 22, Class A Limit).
International	CISPR 22, Class A Limit, Radiated & Conducted Emissions CISPR 24 (Immunity)

Downloaded from www.Manualslib.com manuals search engine

9.3 Regulatory Markings

The SPSH4 server system will be marked with the following regulatory markings.

Table 87: Regulatory Markings

Regulatory Mark	Symbol
cULus Listing Marks	LISTED ITE E139761 c UL us
German GS Mark	Nemko GS geprüfte Sicherheit
CE Mark	CE
FCC Marking (Class A)	This device complies with Part 15 of the FCC Rules. Operation of this device is subject to the following two conditions: (1) This device may not cause harmful interference, and (2) This device must accept any interference received, including interference that may cause undesired operation. Manufactured by Intel Corporation
Canada EMC Marking (Class A)	CANADA ICES-003 CLASS A CANADA NMB-003 CLASSE A
Japan VCCI Marking (Class A)	この装置は、クラス A 情報技術装置です。この装置を家庭環境で使用すると電波妨害を引き起こすことがあります。この場合には使用者が適切な対策を講ずるよう要求されることがあります。VCCI-A
Australia C-Tick Mark	N232
Taiwan BSMI Marking (Class A)	警告使用者：檢磁 3912I902 這是甲類的資訊產品，在居住的環境中使用時，可能會造成射頻干擾，在這種情況下，使用者會被要求採取某些適當的對策



Downloaded from www.Manualslib.com manuals search engine

Russia GOST R Marking	

9.4 Product Safety Markings

The product has been provided with the following safety markings.

Table 88: Product Safety Markings

Safety Mark	Description
	This symbol indicates hazardous voltages. WARNING: Improper use may cause shock hazard. No operator serviceable parts.
	This symbol indicates a general warning, and to refer to manual for warning information
	This symbol indicates fan hazard. WARNING: To reduce risk of injury, do not put fingers into rotating fan blades
	This symbol indicates the system is provided with multiple AC power cords. WARNING: To reduce risk of electric shock, remove all AC power cords to disconnect all power.
	WARNING: To reduce risk of electric shock, system must be connected to an earthed mains socket-outlet

9.5 Power supply Regulatory Agency Certifications

The power supply will have the following:

Safety Compliance

- UL, cuL (USA / Canada) – UL60 950
- German Bauart (Germany) – EN60 950
- CE Declaration of Conformity (Europe)– EU Low Voltage Directive 73/23/EEC
- CB Certificate & Report (International) – IEC60 950 & EMKO-TSE (74-SEC) 207/94
- CCIB Safety (China)

Downloaded from www.Manualslib.com manuals search engine

Emission Compliance

- FCC, Class A Verification (USA/Canada)
- CE Declaration of Conformity (Europe)– EU EMC Directive 89/336/EEC
- EN55022
- EN55024
- EN61000-3-2 & -3-3
- CCIB EMC (China)
- C-Tick (Australia) – AS/NZS 3548

9.6 Regulatory Compliance Notices, Statements and Information

This equipment has been tested and found to comply with the limits for a Class A digital device. These limits are designed to provide reasonable protection against harmful interference when the equipment is operated in a commercial environment. This equipment generates, uses, and can radiate radio frequency energy and, if not installed and used in accordance with the instruction manual, may cause harmful interference to radio communications. Operation of this equipment in a residential area is likely to cause harmful interference, in which case the user will be required to correct the interference at their own expense.

9.6.1 USA FCC Verification Notice

This device complies with Part 15 of the FCC Rules. Operation is subject to the following two conditions: (1) this device may not cause harmful interference, and (2) this device must accept any interference received, including interference that may cause undesired operation.

For questions related to the EMC performance of this product, contact:

Intel Corporation
5200 N.E. Elam Young Parkway
Hillsboro, OR 97124
1-800-628-8686

This equipment has been tested and found to comply with the limits for a Class A digital device, pursuant to Part 15 of the FCC Rules. These limits are designed to provide reasonable protection against harmful interference in a residential installation. This equipment generates, uses, and can radiate radio frequency energy and, if not installed and used in accordance with the instructions, may cause harmful interference to radio communications. However, there is no guarantee that interference will not occur in a particular installation. If this equipment does cause harmful interference to radio or television reception, which can be determined by turning the equipment off and on, the user is encouraged to try to correct the interference by one or more of the following measures:

- Reorient or relocate the receiving antenna.
- Increase the separation between the equipment and the receiver.
- Connect the equipment to an outlet on a circuit other than the one to which the receiver is connected.

Downloaded from www.Manualslib.com manuals search engine

9.6.2 Canada

Cet appareil numérique respecte les limites bruits radioélectriques applicables aux appareils numériques de Classe A prescrites dans la norme sur le matériel brouilleur: “Appareils Numériques”, NMB-003 édictée par le Ministre Canadian des Communications.

English translation of the notice above:

This digital apparatus does not exceed the Class A limits for radio noise emissions from digital apparatus set out in the interference-causing equipment standard entitled “Digital Apparatus,” ICES-003 of the Canadian Department of Communications.

9.6.3 European Union

This product complies with the European Directives, 73/23/EEC – Low Voltage Directive and 89/336/EEC – EMC Directive. The CE Mark is marked on the product to indicate compliance.

9.6.4 Australia / New Zealand

This product complies with AS/NZS 3548, and complies with the Australian Communication Authority and Ministry of Economic Development Regulations. The C-Tick Mark with Intel’s supplier code N232 is marked on the product to indicate compliance.

9.6.5 Japan

この装置は、情報処理装置等電波障害自主規制協議会（ＶＣＣＩ）の基準に基づくクラスＡ情報技術装置です。この装置を家庭環境で使用すると電波妨害を引き起こすことがあります。この場合には使用者が適切な対策を講ずるよう要求されることがあります。


English translation of the notice above:

This is a Class A product based on the standard of the Voluntary Control Council for Interference by Information Technology Equipment (VCCI). If this equipment is used in a domestic environment, radio disturbance may arise. When such trouble occurs, the user may be required to take corrective actions.

Downloaded from www.Manualslib.com manuals search engine

9.6.6 Taiwan

This server complies with CNS13438 and complies with Taiwan BSMI Regulations. The product is marked with the following BSMI Certification number and EMC Warning.



The English translation for the above warning is:

This is a class A product. In a domestic environment this device may cause radio interference in which case the user may be required to take adequate measures.

9.7 Replacing The Back Up Battery

The lithium battery on the server board powers the real time clock (RTC) for up to ten years in the absence of power. When the battery starts to weaken, it loses voltage, and the server settings stored in CMOS RAM in the RTC (for example, the date and time) may be wrong. Contact your customer service representative or dealer for a list of approved devices.

⚠ WARNING
Danger of explosion if battery is incorrectly replaced. Replace only with the same or equivalent type recommended by the equipment manufacturer. Discard used batteries according to manufacturer's instructions.

⚠ ADVARSEL
Lithiumbatteri - Eksplosionsfare ved fejlagtig håndtering. Udskiftning må kun ske med batteri af samme fabrikat og type. Levér det brugte batteri tilbage til leverandøren.

⚠ ADVARSEL
Lithiumbatteri - Eksplosjonsfare. Ved utskifting benyttes kun batteri som anbefalt av apparatfabrikanten. Brukt batteri returneres apparatleverandøren.

⚠ VARNING
Explosionsfara vid felaktigt batteribyte. Använd samma batterityp eller en ekvivalent typ som rekommenderas av apparattillverkaren. Kassera använt batteri enligt fabrikantens instruktion.

⚠ VAROITUS
Paristo voi räjähtää, jos se on virheellisesti asennettu. Vaihda paristo ainoastaan laitevalmistajan suosittelemaan tyyppiin. Hävitä käytetty paristo valmistajan ohjeiden mukaisesti.

Downloaded from www.Manualslib.com manuals search engine

⚠ WARNUNG

Explosionsgefahr bei nicht ordnungsgemãssem Einbau der Batterie. Nur mit gleichen oder vom Hersteller empohlenen Teilen zu ersetzen. Gebrauchte Batterien bitte nach Herstellerangaben entsorgen.

10. Environmental Specifications

The SPSH4 system is tested to the environmental specifications as indicated in Table 89. All testing will be performed per procedures defined in *Intel Environmental Standards Handbook*.

Table 89: Environmental Specifications Summary

Environment	Specification
Temperature operating	10 ° C to 35 ° C
Temperature non-operating	-40 ° C to 70 ° C
Humidity non-operating	90%, non-condensing at temperatures of 25 ° C to 35 ° C
Vibration non-operating	2.2 Grms, 10 minutes per axis on all 3 axes as per *Intel Environmental & Reliability Board and System Validation Test Handbook*
Shock operating	Half-sine 2 G, 11 msec pulse, 100 pulses in each direction, on each of the three axes as per *Intel Environmental & Reliability Board and System Validation Test Handbook*
Shock non-operating	Trapezoidal, 25 G, 175 inches/sec delta V, 2 drops in each direction, on each of the six side as per *Intel Environmental & Reliability Board and System Validation Test Handbook*
Electrostatic discharge (ESD)	Tested to ESD levels up to 15 kilovolts (kV) air discharge and up to 8 kV contact discharge without physical damage as per *Intel Environmental & Reliability Board and System Validation Test Handbook*
Acoustic	Sound pressure: < 55 dBA at ambient temperatures < 28 ° C +/- 2 ° C measured at bystander positions in operating mode Sound power: < 7.0 BA at ambient temperatures < 28 ° C +/- 2 ° C in operating mode
Altitude	0 to 1,520 m (0 to 5,000 ft)

Downloaded from www.Manualslib.com manuals search engine

11. Serviceability and Usability

11.1 Mean Time to Repair

The system is designed to be serviced by qualified technical personnel only.

The desired mean time to repair (MTTR) of the system is 30 minutes including diagnosis of the system problem. To meet this goal, the system enclosure and hardware have been designed to minimize the MTTR.

Following are the maximum times that a trained field service technician should take to perform the listed system maintenance procedures, after diagnosis of the system.

System Component	Total Time	Remove	Replace/Add
Front Cover	1	0.5	0.5
Rear Cover	1	0.5	0.5
Power supply	2	1	1
Hot Swap PCI-X Card	2	1	1
Non-Hot Swap PCI Card	3	1	2
Disk Drive [1]	4	1	3
HPIB Board	4	1	3
Hot Swap Fan [2]	4	2	2
Memory DIMM [3]	4	2	2
Fan PDB	5	2	3
ICMB	5	2	3
CD-ROM	8	4	4
Memory Board	8	4	4
SCSI Drive Bay Fan	9	3	6
Front Panel Board	9	4	5
Floppy	9	4	5
Processor [4]	10	5	5
SCSI Drive Bay	15	6	9
SCSI Backplane	15	6	9
SCSI SAF-TE Board	15	6	9
BaseBoard	16	6	10
Processor Board [5]	20	9	11
Power Distribution Board	30	10	20

Notes:

1. Assumes removal is time required to remove SCSI HDD from System. Replacement time includes time to remove the HDD from the drive carrier and replace with new HDD before reinserting HDD in SCSI Bay.
2. Assumes single fan is removed and replaced in system.
3. Memory DIMM replacement assumes a single DIMM is replaced. Memory DIMM addition assumes four new DIMMs were added to the Memory Board and no DIMMs were removed. This would add an additional minute to the total time.
4. Assumes CPU Board is populated with a single processor and heatsink. If populated with additional processors total time is increased by 4.75 minutes per processor.
5. Assumes single processor is removed.

Downloaded from www.Manualslib.com manuals search engine

11.2 Special Usability Features

- All hot swap user “touch” surfaces color coded green (GE GN3058), these include the power supply, system fans, SCSI hard drive carriers, and hot plug PCI quick release latches
- All non-hot swap user “touch” surfaces color coded blue (Pantone 285C), these include the memory board and processor board latches, processor air duct, bezel door label, and non hot plug PCI quick release latches
- Non user interface internal parts color coded black (GE 701), these include the PCI card guides, rack rails, and peripherial rails
- Corresponding color coding of all appropriate system labels to speed up and ease usability
- LED status indicators provided for the following: power supply, hot plug PCI slots, hard drives, system fans
- AC cord retention hooks to prevent accidental AC power disconnect
- Customizable FRU part number identification label

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Glossary

This appendix contains important terms used in the preceding chapters.

Term	Definition
μF	micro-farad.
μs	micro-second.
Ω	Ohm.
A, Amp	Ampere.
AC	Alternating Current.
ACPI	Advanced Configuration and Power Interface.
ANSI	American National Standards Institute.
APIC	Advanced Programmable Interrupt Controller.
AWG	American Wire Gauge.
BIOS	Basic Input-Output System.
BMC	Bus Management Controller.
Bridge	The circuitry that connects one computer bus to another.
Byte	An 8-bit quantity.
dB	Decibel.
dBA	Decibel (measured using “A” scale).
CD-ROM	Compact Disk – Read Only Memory.
CE	Community European.
CFM	Cubic Feet per Minute.
CISPR	International Special Committee on Radio Interference.
CSA	Canadian Standards Organization.
DAT	Digital Audio Tape (a type of digital media storage tape).
DC	Direct Current.
DIMM	Dual Inline Memory Module.
DMI	Desktop Management Interface.
DOS	Disk Operating System.
DRAM	Dynamic Random Access Memory.
DWORD	Double Word. A 32-bit quantity.
ECC	Error Checking and Correcting.
E-Bay	Electronics Bay
EEPROM	Electrically Erasable Programmable Read-Only Memory.
EMC	Electromagnetic Compatibility.
EMI	Electromagnetic Interference.
EN	European Standard (Norme Européenne or Europäische Norm).
ESCD	Extended System Configuration Data.
ESD	Electrostatic Discharge.
ESR	Equivalent Series Resistance.
FCC	Federal Communications Commission.
Flash ROM	EEPROM.
FRB	Fault Resilient Booting.

Downloaded from www.Manualslib.com manuals search engine

Term	Definition
FRU	Field Replaceable Unit.
G	Acceleration in gravity units, 1G = 9.80665 m/s2.
Grms	Root mean square of acceleration in gravity units.
GB	Gigabyte. 1024 MB.
GPIO	General Purpose Input-Output.
HDD	Hard Disk Drive.
HPIB	Hot Plug Indicator Board.
HSC	Hot-Swap Controller.
I/O	Input/Output.
I2C*	Inter Integrated Circuit bus.
ICMB	Intelligent Chassis Management Bus.
IDE	Integrated Drive Electronics, an interface to drives and storage devices.
IEC	International Electrotechnical Commission.
IEEE	Institute of Electrical and Electronics Engineers.
IFLASH	A utility to update Flash EEPROM.
IMB	Intelligent Management Bus.
IPMB	Intelligent Platform Management Bus.
IPMI	Intelligent Platform Management Initiative.
IRQ	Interrupt Request line.
ITE	Information Technology Equipment.
ITP	In Target Probe.
KB	Kilobyte. 1024 bytes.
L2	Second-level cache.
LAN	Local Area Network.
LED	Light-Emitting Diode.
LVDS	Low Voltage Differential SCSI.
mΩ	milli-Ohm.
mA	milli-Amp.
MB	Megabyte. 1024 KB.
MPS	MultiProcessor Specification.
NEMKO	Norges Elektriske Materiellkontroll (Norwegian Board of Testing and Approval of Electrical Equipment).
NIC	Network Interface Card.
NMI	Non-Maskable Interrupt.
OCP	Over-Current Protection.
OEM	Original Equipment Manufacturer.
OPROM	Option ROM. An expansion BIOS for a peripheral.
OS	Operating System.
OTP	Over-Temperature Protection.
OVP	Over-Voltage Protection.
PC-200	The collection of specifications for 200MHz memory modules.
PCB	Printed Circuit Board.
PCI	Peripheral Component Interconnect, the I/O expansion bus.
PHP	PCI Hot-Plug.

Downloaded from www.Manualslib.com manuals search engine

Term	Definition
PID	Programmable Interrupt Device.
PIRQ	PCI Interrupt Request line.
PMM	POST Memory Manager.
PnP	Plug and play
POST	Power-On Self Test, the BIOS boot code.
PWM	Pulse Width Modulation.
RAS	Reliability, Availability, and Serviceability.
RPM	Revolutions Per Minute.
SAF-TE	SCSI Accessed Fault-Tolerant Enclosures.
SCA	Single Connector Attachment.
SCL	Serial Clock.
SCSI	Small Computer Systems Interface, typically used for storage devices.
SDR	Sensor Data Records.
SDRAM	Synchronous Dynamic RAM.
DDR	Double Data Rate
SEC	Single Edge Contact.
SEL	System Event Log.
SELV	Safety Extra Low Voltage.
SEMKO	Sverge Elektriske Materiellkontroll (Swedish Board of Testing and Approval of Electrical Equipment).
SGRAM	Synchronous Graphics RAM.
SMBIOS	System Management BIOS.
SMBus	A subset of the I2C bus/protocol, developed by Intel.
SMI	System Management Interrupt.
SMM	System Management Mode.
SMP	Symmetric Multiprocessing.
SMRAM	System Management RAM.
SMS	System Management Software.
SPD	Serial Presence Detect. A feature of PC-100 DIMMs that provides configuration information through serial EEPROMs.
SSI	Server System Infrastructure.
TUV	Technischer Uberwachungs-Verein (A safety testing laboratory with headquarters in Germany).
UL	Underwriters Laboratories, Inc.
USB	Universal Serial Bus.
VA	Volt-Amps, Volts multiplied by Amps.
Vac	Alternating Current (AC) Voltage.
Vdc	Direct Current (DC) Voltage.
VCCI	Voluntary Control Council for Interference.
VDE	Verband Deutscher Electrotechniker (German Institute of Electrical Engineers).
VGA	Video Graphics Array.
VRM	Voltage Regulator Module.
VSB	Voltage StandBy.
W	Watt.
WfM	Wired for Management.
Word	A 16-bit quantity.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

12. Index

Downloaded from www.Manualslib.com manuals search engine

Reference Documents

Refer to the following documents for additional information:

- *SSH4 Baseboard, Processor, and Memory Module External Product Specification*, Revision 1.0
- *SSH4 Basic Input Output System (BIOS) External Product Specification*, Revision 1.0
- *Intelligent Chassis Management Bus Bridge Specification*, Revision 1.0
- *Intelligent Platform Management Interface (IPMI) Specification*, Revision 1.5
- *SCSI Accessed Fault-Tolerant Enclosures (SAF-TE) Specification*, Revision 1.0
- *Emergency Management Port Interface External Product Specification*, Revison 1.0
- *SCA-2 Connector Small Form Factor Document 8046,* Rev. 1.1
- *Intel Environmental & Reliability Board and System Validation Test Handbook*, Revision 05

Downloaded from www.Manualslib.com manuals search engine